

SURVEY & REMONUMENTATION

MAY 05 1997

APPROVED DATE 11-20-96 CO. REP. K

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich, P.A. 1970

RECORDED WASHTEAW COUNTY, MI FEB 18 9 11 AM '97 PEARY & HAINES COUNTY CLERK/REGISTER

For corner in Washtenaw (County)

Located in: Corner Code #

- 1. Public Land Survey T 2S R 6E J-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec S T R

Liber 00001 Page 0515

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Charles C. Wilson, in a field survey on November 1, 19 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instruction of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13. Cell (11, J) contains a small circle symbol.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

United States Government Survey, 1815 Instructions, Surveyed 1819 Bearing Trees Hickory 5" S88deg.E 43.56' Meas. (E) 2585.55' (W) 2585.55'

H.H. Atwell, PS #322, Date Unknown Washtenaw County Road Commission Grid Book Book 534, Page 14 48.0' WEST to East Edge of Pond 186.5' NORTH to South Edge of Huron River 3" Cherry 59.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 4" Diameter x 30" Concrete Shaft encased in Metal and surrounded with Stone from information and accessories mentioned in Paragraph A.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Re-Set Found Concrete Shaft with a 1" X 24" Iron Pipe with a Remonumentation Cap Stamped #13604 48 feet WEST to East Edge of Pond * 24" Oak S22deg.E 130.50' (Nail & RT) 4" Oak N73deg.E 75.71' (Nail & RT) Center of Well Pump Pipe N76deg.E 97.86' SE Corner of Post at NW'ly Corner of Park Pavilion N74deg.E 130.02' SW Corner of Post at SW'ly Corner of Park Pavilion N53deg.E 124.25' * Indicates accessory previously mentioned in Paragraph A RT Indicates Remonumentation Tag

I believe this point should be accepted as the best availabel evidence of the position of the original corner. This point was ratified by the Washtenaw County Peer Committee on November 20, 1996.

COPY



Signed by [Signature] Surveyors Michigan's License No. 13604

Date November 21, 1996