

**SURVEY &
REMONUMENTATION**

**MAY 09 1996
COMMISSION**

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

- Copy -
RECORDED
WASHTENAW COUNTY, MI
MAR 29 1 38 PM '96
COUNTY CLERK / REGISTER
COPY

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>6E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, R.T. Tietsema in a field survey on 12/17 19 95, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered. found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

1817	GLO	Fld. Notes	Set Original Corner			
				1) 48" W. Oak	S22W	40 links (26.4')
				2) 12" Hickory	N09E	55 links (36.30')
8/20/1934	W.J. Armstrong		Fnd an Iron Pipe inside a 4" tile. Reset with a 1 1/2"x42" iron pipe, stones, and bricks.	3) 6" Hickory		North 66.2'
				4) 8" Forked Hickory		N01W 69.6'
				5) 8" Twin Hickory		N01E 80.7'
				6) 24" Forked Elm		N76E 118.6'
				7) NE Post Section 2 T3S, R6E		West 245.5'
9/18/1974	Robert J. Jacow	6998 L3P533	Fnd. 3/4" Iron Pipe	4) 10" Forked Hickory	N01W	69.6'
				5) 10" Twin Hickory	N01E	80.7'
				8) 8" Hickory	North	55.2'
				9) NW Cor Bldg.	S20E	163.2'
8/12/1994	Allen R. Rentschler JOB NO: 94167	15411	Boundary Fnd. 1 1/4" Iron Pipe	9) NW Cor Bldg	S20E	163.25'
				10) U. Pole		Due West 44.73'
				11) 12" Pine	N15E	35.00'
				12) 12" Hickory		Due South 55.02'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/4" Iron Pipe
Also found remaining witnesses:

9) NW Cor Bldg	S20E	163.25'
10) U. Pole	Due West	44.73'
11) 12" Pine	N15E	35.00'
12) 12" Hickory	Due South	55.02'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap on existing 1 1/4" Iron Pipe
Also set additional accessories:

13) North edge of Asphalt	South	14.5'
------------------------------	-------	-------

APPROVED
DATE 12/11/95
CO. REP. [Signature]

It is my opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by [Signature] Date 18 DEC. 95
Surveyor's Michigan License No. 20712