

SURVEY &
REMONUMENTATION

NOV 02 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW
(County)

Located In: _____

Corner Code # _____

1. Public Land Survey T _____ R _____
ANN ARBOR TWP T _____ R _____
T _____ R _____
T _____ R _____

2. Property controlling S 1 T 2 S R 6 E L-1
in Section S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



5017343
Page: 1 of 2
02/25/1999 02:59P
L-2 P-250

Copy
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, LORI E. BEYER, in a field survey on NOVEMBER 15, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

N 1/4 CLOSING CORNER OF SECTION 1 AS MONUMENTED
1998 REMONUMENTATION PROGRAM

A. Description of original monument and accessories and/or subsequent restoration:

ATWELL HICKS - OCT. 1955 - HODGSON - FLD BK. B. 620 PP. 36-38
SET 1" IRON PIPE ON LINE BETWEEN THE SW AND SE CORNERS OF SEC 36 SUPERIOR TWP
AND MIDWAY BETWEEN THE NE & NW CORS OF SEC 1 ANN ARBOR TWP

(1) 8" HICKORY	S 04° E	34.0'
(2) 16" HICKORY	N 27° E	34.7'
(3) 18" HICKORY	N 55° W	56.5'
(4) 16" HICKORY	N 65° W	63.3'
(5) 32" W. OAK	S 74° W	64.9'
(6) 12" HICKORY	S 51° W	34.3'
(7) 16" HICKORY	S 48° W	38.6'

Continued on Back

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

FOUND A 3/4" IRON BAR 5" BELOW GRAVEL +/- 4' SOUTH OF
NORTH EDGE OF GRAVEL OF JOY ROAD.
PLACED ALUMINUM REMON. CAP OVER IRON BAR.
FOUND SEVEN (7) REMAINING WITNESSES.

(4) 24" DEAD HICKORY	N 65° W	63.47'	FD NAIL S/S
(3) 24" DEAD HICKORY	N 55° W	56.5'	TO CTR S/S

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" IRON BAR WITH ALUMINUM REMON. CAP 5" BELOW GRAVEL ROAD.

(5) 45" OAK	S 74° W	64.86'	SET MAG NAIL AND WASHER N/S
(10) 7" ASH	N 73° W	59.37'	SET MAG NAIL/WASHER W/S
(8) S 1/4 SEC 36 NORTHFIELD	EAST	261.62'	TO FD IRON PIPE
(1) 18" HICKORY	S 04° E	35.2'	TO CTR W/S
(9) 8" ASH	N 60° E	36.44'	SET MAG NAIL/WASHER W/S
(2) 28" HICKORY	N 27° E	33.82'	SET MAG NAIL/WASHER OVER FD PK W/S (FD NAIL 34.5')
(11) WOOD FENCE POST	SOUTH	30.29'	SET MAG NAIL/WASHER E/S
(12) 9" B. CHERRY	N 09° E	26.59'	SET MAG NAIL/WASHER OVER FD NAIL

THIS CORNER WAS NOT ESTABLISHED BY THE ORIGINAL GOVERNMENT LAND OFFICE BUT WAS SET SUBSEQUENTLY USING PROPER METHOD BY A QUALIFIED SURVEYOR. I BELIEVE THIS POINT TO BE THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

THIS POINT WAS RATIFIED BY THE PEER REVIEW COMMITTEE ON DEC. 14, 1998.

Signed by Lori E. Beyer Date Dec. 15, 1998
Surveyor's Michigan License No. 41092

APPROVED
DATE 12-14-98
CO. REP. _____

COPY



5017343
Page: 2 of 2
02/25/1999 02:59P
L-2 P-251

L-1

Continued from Section A:

- Copy -

Robert M. Pitts - RLS #10702 - 1987 - L.C.R.C. I. 7, P.242
Found 3/4" Iron Bar

(2) 22" Hickory	N 01° E	33.91'	pk nail w/s
(9) 8" Ash	N 54° E	36.52'	pk nail se/s
(7) 20" Hickory	S 43° W	38.12'	pk nail e/s
(5) 40" Oak	S 68° W	65.22'	pk nail nw/s

**SURVEY &
REMONUMENTATION**

NOV 02 1999

Midwestern Consulting Inc. - Field Book - 1988
Found 1" Iron Pipe. Raised to surface with 3/4" Iron and cap

SECTION

(8) S 1/4 Cor Sec 36 Northfield East 262.05'

Allen Rentschler -RLS #15411 - P.A. 132 Unrecorded - Shows found. No witnesses posted.