

SURVEY & REMONUMENTATION

- Copy -

MAY 09 1996

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

_____ Washtenaw _____ (county)	Located in:	Corner Code #
1. Public Land Survey	T 2S R 6E	L-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTERED
 WASHTENAW COUNTY, MI
 MAR 29 1 39 PM '96
 COUNTY OF DEEDS REGISTER
 - COPY -

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, R.T. Tietsema, in a field survey on 12/17, 1995, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

1817	GLO	Field Notes	Set Original Corner	1) 18" W. Oak	S83E	114 links (75.24')
			No other bearing trees found			
8/20/1934	W.J. Armstrong		1" Iron Pipe	2) 14" Maple	S63E	59.3'
				3) 16" Maple	S38E	33.5'
				4) 6" Twin Y.O.	S20W	31.6'
				5) 14" Maple	S61W	51.3'
				6) 30" Maple	S72W	82.1'
				7) 16" W. Oak	N05E	70.2'
5/23/1974	Robert J. Jagow	6998 L3P533	Find 3/4" Iron Pipe in mon. box	2) 20" Maple	S63E	59.5'
				3) 22" Maple	S32E	33.5'
				4) 14" & 16" Twin Oak	S20W	31.6'
12/13/1976	J. Serafin		1" Iron Pipe	3) 24" Maple	S38E	34.08'
				4) 6" Twin Maple	S19W	32.46 to nail
				5) 20" Maple	S60W	50.85 to nail
				8) Power Pole	N57W	61.38' to nail

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron Pipe in pavement, also nails in pavement 1.5' N,E,S,W of corner.
 Also found remaining witnesses:

4) 14" & 16" Twin Oak	S20W	31.12' to nail
9) 14" Oak	S04E	30.36'
10) 7" Ash	S44W	49.38'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap on existing 3/4" Iron Pipe in pavement.
 Also set additional accessories:

11) Fence Post	North	32.46'
12) 3/4" Iron Rod	East	122.91'
(N 1/4 Corner Sec. 1 T3S,R6E)		

APPROVED

DATE 12/11/95

CO. REP. 14

It is my opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R. Tietsema Date 18 Dec. 95
 Surveyor's Michigan License No. 20712

- Copy -

Section A continued

6/22/1984	R.A. Cambell, JR	13028	L7P121	Fnd 3/4" Iron Pipe in mon. box	2) 20" Maple S63E 59.5' 3) 22" Maple S32E 33.5' 4) 14" & 16" Twin Oak S20W 31.6'
8/12/1994	Allen R. Rentschler	15411		Fnd. 1" Iron Pipe	2) 22" Dead Maple S45E 59.65' 4) 20" Twin Oak S20W 31.10' 3) 24" Dead Maple S35E 34.20' 9) 14" Oak S10E 30.25'
8/18/1994	K.M. Anderson.	37269		3/4" Iron Pipe	2) 24" Maple S63E 60.0' 3) 24" Maple S32E 33.8' to nail 4) 14" & 16" Twin Oak S20W 31.12' to nail 10) 14" Oak S04E 30.36' 11) 7" Ash S44W 49.38'

APPROVED

DATE _____

CO. REP. _____