

SURVEY & REMONUMENTATION

MAY 09 1996

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

- Copy -

For corners in

Washtenaw Located In: Corner Code #
(county)

1. Public Land Survey T 2S R 6E M-13 ✓
 T 35 R 6E M-1
 T 25 R 7E A-13
 T 35 R 7E A-1

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

RECORDED
 WASHTENAW COUNTY, MI
 MAR 29 1 39 PM '96
 DEPT. OF TREASURY
 COUNTY CLERK/REGISTER
 - COPY -

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, R.T. Tietsema, in a field survey on 12/17, 1995, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

Date	Name	Id.	Notes	Set Original Corners	1) 24" W. Oak	N10W	12 links (7.92')
1817	GLO				2) 24" W. Oak	S10E	39 links (25.74')
				Set post corner of T2&3, R 6&7E			
Unknown	H.H. Atwell			Iron Pipe	3) 14" Elm	SW	41.9'
					4) 18" Hickory	W of S	65.5'
					5) 8" Forked Cherry	SE	50.8'
					6) Conc. Post	North	24.7' to south side
12/14/1988	R.A. Campbell, JR	13028	L7P203	Fnd. 3/8" bar in pvmt. Reset with 3/4"x18" Iron Pipe with cap in mon. box	7) U. Pole	S40E	65.42' to PK nail
					8) Manhole	SLY	16.8' to center
					9) Hydrant	S67W	72.78' to top nut
					10) Top of SW cor. conc. pad traffic control box	N42E	75.08'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" capped (non-readable) Iron Pipe in Mon. Box.
 Also found remaining accessories:

7) U. Pole	S40E	65.42' to PK nail
8) Manhole	SLY	16.8' to center
9) Hydrant	S67W	72.78' to top nut
10) Top of SW cor. conc. pad traffic control box	N42E	75.08'

APPROVED
 DATE 12/11/95
 CO. REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap on existing 1" capped (non-readable) Iron Pipe in Mon. Box.

It is my opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date 18 Dec. 95
 Surveyor's Michigan License No. 20712