

SURVEY &  
REMONUMENTATION

MAY - 1 1995

COPY

RECORDED  
WASHTENAW COUNTY, MI

JAN 10 9 39 AM '95

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Washtenaw  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 2S R 7E      K-9  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

PEGGY W. HAINES  
COUNTY CLERK/REGISTER  
-COPY-

LIBER      1 PAGE 229 RM  
-COPY-  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kenneth R. Coleman in a field survey on December 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
See back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1 1/2" I.P. w/brick pieces. Removed and reset w/1" x 2' I.P. w/remon. cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
See back



Signed by Kenneth R. Coleman Date 12-28-94  
Surveyor's Michigan License No. 37271

- copy -

K-9, T2S, R7E

Y-100

A. No date                      K. Barker                      Wash. Co. Grid Book  
 3/4" pipe surrounded by brick  
 3) T. pole    N47°E                      28.7  
 4) Iron pipe on E & W fenceline                      S87°E                      33.00  
 5) B.M. on triple 10" T. Apple                      S51°W                      44.75

8-31-1942                      Warner & Warner                      Survey  
 No witnesses

12-19-1950                      Atwell-Hicks, Inc.                      Field Book 583-59  
 Found  
 5) Triple thorn    S45°W                      45.0  
 6) 1" I.P.    N45°W                      46.8  
 7) 1" I.P.    S45°W                      47.0  
 8) West road fence    WEST                      33.0  
 9) East road fence    EAST                      34.7  
 10) South road fence line west                      SOUTH                      21.8  
 11) North road fence line west                      NORTH                      23.3

6-17-1958                      Atwell-Hicks, Inc.                      Field Book 605-51  
 Used in survey - No witnesses

C. Found 1 1/2" iron pipe with brick pieces. Removed and set 1' x 2" I.P. w/remon. cap.

7) 1" bent iron pipe	S45°W	47.04
8) West road fence north	WEST	33.0
11) North road fence west	NORTH	26.4
12) P. pole	N18°E	110.34 to nail w/W.C.R. tag
13) P. pole	S 9°E	214.34 to nail w/W.C.R. tag
14) Stop sign	S71°W	37.5
15) 4" steel mail box post	N33°E	37.9
16) South street sign pole	EAST	24.7

I conclude that this corner is accepted as the best available evidence of the position of the original corner.

APPROVED

DATE 12/19/94

DED

VA