

**SURVEY & REMONUMENTATION**


**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 02 1999

For corners in

SECTION

<u>WASHTENAW</u> (County)	Located In:	Corner Code #
	SHARON TOWNSHIP	
1. Public Land Survey	T <u>3S</u> R <u>3E</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____



5017313  
Page: 1 of 2  
02/25/1999 02:59P  
Peggy M. Haines - Washtenaw Co. CORREM L-2 P-192  
**COPY**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL V. SCHWIMMER, in a field survey on OCT 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.D. WITNESSES FROM NOTES (1816) SET 1/4 CORNER POST  
W. OAK 48° N 73°E 43 LINKS (1) (GONE)  
W. OAK 20° S 30°W 20 LINKS (2) (GONE)

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" IRON IN MONUMENT BOX FROM PREVIOUS WITNESSES. I DROVE AN ALUM. REMONUMENTATION CAP ONTO THE IRON.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 W 1/4 CORNER OF SECTION 24 SHARON TOWNSHIP  
FOUND 1 1/4" IRON IN MONUMENT BOX. SET ALUMINUM REMONUMENTATION CAP ON IRON.  
IRON IS IN C/L OF ASPHALT M-52  
S 60°W 28.76' (MEAS 28.51') 40" OAK WITH NAIL & TAG (7)  
N 55°W 31.25' (MEAS 31.20') 18" OAK WITH NAIL & REMON TAG (5)  
N 82°E 32.75' (MEAS 32.77') TOP CENTER OF CONC. POST (6)  
S 60°E 38.49' (MEAS 38.80') CENTER OF 44' STUMP (9)  
N 80°W 26.45' N.E. CORNER OF 8'X8" CONC. POST



Signed by Paul V. Schwimmer  
Surveyor's Michigan License No. 29618

Date 12-07-1998

**COPY**

APPROVED  
DATE 12-14-98  
CO. REP. HP

SURVEY &  
REMONUMENTATION

NOV 02 1999

SECTION

At

9\20\1978 ACT 74 RECORDED IN LIBER 5, PAGE 135  
FOUND 1 1/4" IRON PIPE, RESET IN MON. BOX (3)  
S 60°W 28.76 38" OAK (4)  
N 55°W 31.25 14" OAK (5)  
N 82°E 32.75' TOP CENTER CONC. POST (6)  
S 60°E 38.49' 44" OAK (7)  
CORNER IS IN CENTERLINE OF ASPHALT

10-27-1980 ATWELL-HICKS SURVEY DRAWING 547-88, RECORDED IN LIBER 1783, PAGE 783

FOUND 3/4" IRON PIPE IN MON. BOX (3)  
S 40°W 28.6' 38" OAK (7)  
N 80°W 26.2' 14" ASH (8) (GONE)  
N 70°W 31.4' 14" ASH (5)  
S 50°E 38.4 42" OAK (9) (STUMP)

9-1988 LAND SURVEYING CONSULTANTS SHOWS THIS CORNER ON A DRAWING  
WITH JOB NO. 17987-3S4E13. NO WITNESSES AVAILABLE.

10-24-1990 WASHTENAW ENGINEERING DRAWING JOB NO. 23132

FOUND 1" IRON IN MONUMENT BOX (3)  
S 45°W 28.51' 36" OAK (7)  
N 45°W 31.20' 16" OAK (5)  
S 45°E 28.35' 46" OAK (9) (STUMP)  
N 75°E 35.73' 10" BASSWOOD (10) (GONE)

3-25-1991 SURVEY BY C. WILSON & ASSOC. JOB NO. 91010

1 1/4" IRON PIPE IN MON. BOX (3)  
S 60°W 28.76' 38" OAK (7)  
N 55°W 31.25' 14" OAK (5)  
N 82°E 32.75' TOP CENTER CONC. POST (6)  
S 60°E 38.49' 44" OAK (9) (STUMP)  
N 60°E 35.70' 12" WALNUT (10) (GONE)

11-17-1993 WASHTENAW ENGINEERING DRAWING JOB NO. 24730

FOUND 1" IRON IN MONUMENT BOX (3)  
S 45°W 28.51' 36" OAK (7)  
N 45°W 31.20' 16" OAK (5)  
S 45°E 28.35' 46" OAK (9) (STUMP)  
N 75°E 35.73' 10" BASSWOOD (10) (GONE)



5017313

Page: 2 of 2

02/26/1999 02:59P

Peggy M. Haines - Washtenaw Co. CORREM L-2 P-193

*copy*