

MAY 09 1996

- Copy -

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>3E</u>	<u>K9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTERED
 WASHTENAW COUNTY, MI
 MAR 29 1 30 PM '96
 COUNTY CLERK
 REGISTER OF DEEDS
 Stamp & File Number

I, R.T. Tietsema in a field survey on May 31, 19 95, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered. found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

1815	GLO (Wampler)	Fld. Notes	Set Original Corner	1) 12" W. Oak 2) 9" Y Oak	S48E N20W	67 links (44.20) 17 links (11.22)
			Set Corner for Sections 23,24,25, & 26			
12/5/1923	WCRC		Fnd. square bolt level with blacktop surface at corner of M-52 & Pleasant Lake Road	3) SE Cornerstone of Salem Church 4) 20" B. Oak 5) 14" Maple	N45W S35E N09E	74.0' 47.13' 184.33"

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found square bolt in monument box. Intersection of M-52 and Pleasant Lake Road.

Also found remaining witnesses:

3) Cornerstone Salem Church	N45W	73.86'	
9) Power Pole	S45E	61.89'	
10) Power Pole	N45E	64.28'	
11) Power Pole	S45W	63.45'	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap on existing square bolt

Set addition accessories:

3) Cornerstone Salem Church	N45W	73.86'	
9) Power Pole	S45E	61.89'	to nail & R.T.
10) Power Pole	N45E	64.28'	to nail & R.T.
11) Power Pole	S45W	63.45'	to nail & R.T.

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date 11 DEC. 95
Surveyor's Michigan License No. 20712

-copy-

Section A continued

Date	Name	Lot	Sublot	Boundary	Description	Witnesses	Measurements
3/17/1976	R.T. Tietsema	20712			Fnd. Iron (square top) at Centerline M-52 & Pleasant Lake Rd	3) SE Corner Salem Church N44W 6) SW Corner Salem Church N63W 7) ROW Marker S43E 8) 14" Cherry S22E	73.65' 100.93' 44.50' to center 83.71' to spike
3/09/1978	Douglas W. Hooth	7966	L5P136		Inst. mon. box with sq. bolt witnesses	3) SE Corner Church N45W 8) 21" W. Cherry S15E 9) Power Pole S45E	73.60' 83.60' 62.43'
2/15/1979	John L. Synder	13352	L5P162		Fnd 3/4" iron pipe in mon. box	3) SE Corner Church N40W 8) 22" Cherry S20E 9) Power Pole S45E	73.72' 83.8' 62.6'
12/20/1982	Thomas Sutherland JOB NO: 18498	24620	L6P297	Boundary	Fnd bolt in mon. box	3) SE Cornerstone Salem Church N45W 9) Power Pole S45E 10) Power Pole N45E 11) Power Pole S45W	73.65' 62.76' to flasher 63.76' to nail 62.98' to nail
5/1/1986	N.N. Fahrner JOB NO: 20593	17620		Boundary	Fnd bolt in mon. box	3) SE Cornerstone Salem Church N45W 9) Power Pole S45E 10) Power Pole N45E 11) Power Pole S45W	73.65' 62.76' to flasher 63.76' to nail 62.98' to nail
10/24/1990	N.N. Fahrner JOB NO: 23132	17620		Boundary	Fnd bolt in mon. box	3) SE Cornerstone Salem Church N45W 9) Power Pole S45E 10) Power Pole N45E 11) Power Pole S45W	73.65' 62.45' to flasher 63.76' to nail 62.98' to nail
10/14/1992	N.N. Fahrner JOB NO: 24147	17620		Boundary	Fnd. bolt in mon. box	3) SE Cornerstone Salem Church N45W 9) Power Pole S45E 10) Power Pole N45E 11) Power Pole S45W	73.65' 62.45' to flasher 63.76' to nail 62.98' to nail
3/31/1993	Charles C. Wilson JOB NO: 93009	13604		Boundary	Fnd. square bolt in mon. box	3) SE Cornerstone Salem Church N45W 9) Power Pole S45E 10) Power Pole N45E 11) Power Pole S45W	73.65' 62.45' to flasher 63.76' to nail 62.98' to nail
11/17/1993	Thomas Sutherland JOB NO: 24730	24620		Boundary	Fnd bolt in mon. box	3) SE Cornerstone Salem Church N45W 9) Power Pole S45E 10) Power Pole N45E 11) Power Pole S45W	73.65' 62.45' to nail 63.76' to nail 62.98' to nail
3/4/1994	N.N. Fahrner JOB NO: 24911	17620		Boundary	Fnd. bolt in mon. box	3) SE Cornerstone Salem Church N45W 9) Power Pole S45E 10) Power Pole N45E 11) Power Pole S45W	73.65' 62.45' to flasher 63.76' to nail 62.98' to nail

APPROVED
 DATE 10/23/95
 CO. REP. 10/23/95