

SURVEY &
REMONUMENTATION

MAY 09 1996

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>3E</u>	<u>K10</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED
 WASHTEENAW COUNTY, MI
 MAR 29 1 31 PM '96
 COUNTY CLERK/REGISTER
 - COPY -

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, R.T. Tietsema, in a field survey on June 19, 1995, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

1815	GLO (Wampler)		Fld. Notes	Set Original Corner	1) 14" Y. Oak 2) 8" Y Oak	N27E S27W	61 links (40.26') 1.90 chains (12')
				Set 1/4 Section Post			
11/28/1979	Norman N. Fahrner JOB NO:18498	17620	L5P271	Fnd 1/2" Iron Pipe	3) Pipe Line Marker 4) 30" Maple 5) SW Corner MBT Box 6) Pipe Line Marker 7) Fence corner	N25E N35E S85E N45W N80W	47.0' 69.25' to nail 27.5' 45.00' 27.83' to nail

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 3" Iron Pipe 1" below asphalt, at the centerline of M-52
 Pulled and found nothing below it.
 Also found remaining witnesses:

3) Pipe Line Marker	N25E	46.8'
5) SW Corner MBT Box	S85E	29.0'
6) Pipe Line Marker	N45W	45.46'
7) Fence Corner	N85W	28.19' to nail on N. side

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 1" Iron Pipe and Remonumentation Cap

Set additional accessories:

8) Power Pole	N75W	37.39' to nail on N. side
9) Power Pole	N85E	35.36' to nail on N. side
10) 14" Oak	S80E	32.14' to nail on S. side

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by *R. T. Tietsema* Date 11 Dec. 95
 Surveyor's Michigan License No. 20712

- Copy -

Section A continued

Date	Owner	Lot	Block	Marker	Marker	Marker	Marker	Marker	Marker	Marker	Marker	Marker	Marker	Marker					
1/1986	Norman N. Fahrner JOB NO: 20593	17620	L5P271	Fnd 1/2" Iron Pipe	3) Pipe Line Marker	N25E	47.0'	4) 30" Maple	N35E	69.25' to nail	5) SW Corner MBT Box	S85E	27.90'	6) Pipe Line Marker	N45W	45.00'	7) Fence corner	N80W	27.83' to nail
11/1993	Thomas Sutherland JOB NO: 18498	24620	Boundary	Fnd. 1/2" Iron Pipe	3) Pipe Line Marker	N25E	47.0'	4) 30" Maple	N35E	69.25' to nail	5) SW Corner MBT Box	S85E	27.90'	6) Pipe Line Marker	N45W	45.00'	7) Fence corner	N89W	27.83' to nail
4/1994	Norman N. Fahrner JOB NO: 24911	17620	L5P271	Fnd 1/2" Iron Pipe	3) Pipe Line Marker	N25E	47.0'	4) 30" Maple	N35E	69.25' to nail	5) SW Corner MBT Box	S85E	27.90'	6) Pipe Line Marker	N45W	45.00'	7) Fence corner	N80W	27.83' to nail

RECORDED
 WASHINGTON COUNTY, MI
 MAR 29 1 31 PM '95
 PEGGY A. JAMES
 COUNTY CLERK/REGISTRAR

APPROVED
 DATE 10/23/95
 CO. REP. KX