

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 02 1999

For corners in

WASHTENAW  
(County)

Located In: SHARDN TOWNSHIP

Corner Code #

SECTION

1. Public Land Survey

T 3S R 3E L-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

5017315  
Page: 1 of 2  
02/25/1999 02:59P  
Peggy M. Haines - Washtenaw Co. CORREM L-2 P-196  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, PAUL V. SCHWIMMER, in a field survey on OCT 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.D. WITNESSES FROM NOTES (1816) SET 1/4 POST  
Y. OAK 18" N 84°W 2.60 CHAINS (1) (GONE)  
W. OAK 13" S 81°E 1.42 CHAINS (2) (GONE)

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND SURVEYOR WILSON'S 1 1/2" IRON PIPE FROM THE ABOVE ACCESSORIES.



THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 S 1/4 CORNER OF SECTION 13 SHARDN TOWNSHIP  
FOUND 1 1/2" X 48" IRON PIPE IS WETLANDS AREA, REPLACED WITH 2" X 18" IRON WITH ALUM. REMON. CAP  
N 10°W 38.88' (MEAS 38.90) 14" OAK WITH NAIL & REMON. TAG (4)  
N 30°E 39.82' (MEAS 39.72') 12" CHERRY WITH NAIL & REMON. TAG (5)  
ELY' 22.35' (MEAS 22.44') 26" CHERRY WITH NAIL & REMON. TAG (6)  
S 10°E 36.00' (MEAS 36.02') TWIN 16" CHERRY WITH NAIL & REMON. TAG (7)  
S 40°W 26.70' (MEAS 26.74') 18" CHERRY WITH NAIL & REMON. TAG (8)  
S 43°W 29.64' 16" CHERRY WITH NAIL & REMON. TAG

Signed by Paul V. Schwimmer  
Surveyor's Michigan License No. 24618

Date 12-07-1998

COPY

APPROVED  
DATE 12-14-98  
CO. REP. [Signature]

A:

3-24-1991 ACT 74 RECORDED UNDER LIBER 7, PAGE 272, BY SURVEYOR CHARLES WILSON DESCRIBED MR. WILSON'S EFFORTS IN RESETTING THIS CORNER. HE STATES: 'ESTABLISHED TEMPORARY POINT AT THE INTERSECTION OF THE RANGES OF FENCE LINES N-E-S-W. CHECKED THIS LOCATION AGAINST PREVIOUS MEASUREMENTS MADE BY AMERICAN ENGINEERING CO. (1965), ALTON SIMMS, R.L.S. (1950'S), AND RUSSELL WHIPPLE (1853). THIS LOCATION MATCHES, VERY CLOSELY, WITH THESE PREVIOUS MEASUREMENTS. DUG EXTENSIVELY IN THIS AREA WITH NO RESULTS. THIS LOCATION IS APPROXIMATELY 20' WEST OF A MID-POINT BETWEEN THE SECTION CORNERS. ALSO DUG AT THIS MID-POINT WITH NO RESULTS. REMAINING EVIDENCE OF BEARING TREES IS NON-EXISTANT. SUBSEQUENT DIVISION OF SECTION 24, USING THIS LOCATION, INDICATES VERY CLOSE RELATIONSHIPS OF SURVEY LINES TO EXISTING LINES OF OCCUPATION. I, THEREFORE, SET A 1 1/2' X 48' IRON PIPE AT THIS LOCATION FOR L-7.'

SET 1 1/2' X 48' IRON PIPE (3)  
N 10°W 38.88' 14' DAK WITH NAIL (4)  
N 30°E 39.82' 12' CHERRY WITH NAIL (5)  
ELY' 22.35' 24' CHERRY WITH NAIL (6)  
S 10°E 36.00' TWIN 16' CHERRY WITH NAIL (7)  
S 40°W 26.70' 18' CHERRY WITH NAIL (8)



5017315

Page: 2 of 2

02/25/1999 02:59P

Peggy M. Haines - Washtenaw Co. CORREM L-2 P-197

- COPY -

SURVEY &  
REMONUMENTATION

NOV 02 1999

SECTION