

**SURVEY &
REMONUMENTATION**

MAY 09 1996

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

- Copy -

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>3E</u>	<u>L9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED
 WASHTEENAW COUNTY, MI
 MAR 29 1 32 PM '96
 COUNTY CLERK/REGISTRAR
 - COPY -

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, R.T. Tietsema, in a field survey on May 31, 1995, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

1815	GLO (Wampler)	Fld. Notes	Set Original Corner	1) 6" Hickory 2) 14" Y Oak	S75E N31W	76 links (50.16') 36 links (23.76')
			Set 1/4 Section Post			

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2: Capped Iron Pipe (#20709)
 Also found remaining witnesses:
 4) 30" Maple South 16.40'
 6) 3/4" Iron Pipe East 13.62'
 8) 6" Cherry N50W 15.12'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 1" Iron Pipe with Remonumentation Cap
 Set additional accessories:
 4) 30" Maple South 16.40' to nail & R.T.
 6) 3/4" Iron Pipe East 13.62'
 8) 6" Cherry N50W 15.12' to nail & R.T.
 9) 6" Cherry East 33.40' to nail & R.T.

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by *R. Tietsema* Date 11 Dec. 95
 Surveyor's Michigan License No. 20712

-copy-

Section A continued

Date	Name	Parcel	Notes	Marker	Dimensions	Orientation	Remarks
0/26/1976	Jack N. Owens	20709	L4P187	Set 1/2"x18" Iron at Bottom of Road Berm Used line from SE corner to WCRC P.I. for Pleasant Lake Road as South line of section. Used range of N-S 1/4 line fence southerly. Used intersection of these lines as best evidence of original location of corner.	3) 3" Cherry 4) 22" Maple 5) Steel Angle Post 6) 1" Iron at (WCRC.P.I. Pleasant Lake Road)	N80E S05E	6.08' to nail 16.58' to nail E. Side South 15.09' East 13.50'
10/1984	Paul Schwimmer JOB NO:35279	24618	Boundary	Fnd. 1/2" Iron	3) 4" Cherry 4) 22" Maple 5) Steel Fence Post 6) 1" Fnd iron at WCRC P.I.	N80E S05E SLY	6.08' to nail 16.58' to nail 15.09' East 13.60'
1/1986	N.N. Fahrner JOB NO:20593	17620	Boundary	Fnd. 1/2" Iron Pipe	4) 30" Maple 6) 3/4" Iron Pipe 7) 6" Cherry 8) 6" Cherry	South East S35E N50W	16.12' to nail 13.62' 13.04' to nail 15.10' to nail
1/17/1993	Thomas Sutherland JOB NO:24730	24620	Boundary	Fnd. 1/2" Iron Pipe	4) 30" Maple 6) 3/4" Iron Pipe 7) 6" Cherry 8) 6" Cherry	South East S35E N50W	16.12' to nail 13.62' 13.04' to nail 15.10' to nail
4/1994	N.N. Fahrner JOB NO:24911	17620	Boundary	Fnd. 1/2" Iron Pipe	4) 30" Maple 6) 3/4" Iron Pipe 7) 6" Cherry 8) 6" Cherry	South East S35E N50W	16.12' to nail 13.62' 13.04' to nail 15.10' to nail

APPROVED
 DATE 10/23/95
 CO. REP. [Signature]