

SURVEY &  
REMONUMENTATION

MAY 09 1996

COMMISSION

Liber 000001 Page 0435

- Copy -

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Washtenaw _____ (county)	Located in:	Corner Code #
1. Public Land Survey	T 3S R 3E	L11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED  
 WASHTENAW COUNTY, MI  
 MAR 29 1 32 PM '96  
 COUNTY CLERK'S REGISTER  
 COPY -

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, R.T. Tietsema, in a field survey on May 31, 1995, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:

1815	GLO (Wampler)	Fld. Notes	Set Original Corner	1) 10" W. Oak	N44W	40 links (26.40')
			Set 1/4 Section Post	2) 10" Y Oak	S07E	1.44 chains (67')
12/18/1933	W.J. Armstrong		Fnd post, Reset with iron pipe, bricks and stones.	3) 20" Spruce	N38W	90.1'
				4) SE Corner Hisc	N11.5W	99.2'
				5) 6" Pear	N11E	72.6'
				6) 6" Hickory	S78.5E	128.0'
				7) 18" Cherry	S02W	79.9'

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" Bent Iron Pipe with small pieces of brick, at intersection of Bethel Church Road and Parr Road.  
 Also found remaining witnesses:  
 9) Face Wood Fence Post S68E 67.1'  
 11) SE Corner Bar-B-Q Pit N54W 98.4'  
 16) SW Corner Barn Foundation N40E 111.4'  
 17) U. Pole S45W 75.88'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 1" Iron Pipe and Remonumentation Cap  
 Set additional accessories:  
 9) Face Wood Fence Post S68E 67.1' to nail & R.T.  
 11) SE Corner Bar-B-Q Pit N54W 98.4'  
 16) SW Corner Barn Foundation N40E 111.4'  
 17) U. Pole S45W 75.88' to nail & R.T.

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by [Signature] Date 11 DEC. 95  
 Surveyor's Michigan License No. 20712

- Copy -

Section A continued

Date	Name	Address	Lot	Boundary	Foundation	Notes	Dimensions
23/1972	James H. Granger	16041		Boundary	Fnd. 1 1/2" Iron Pipe	8) Wood Fence Post N51E 9) Wood Fence Post S68E 10) U. Pole S41W 11) SE Corner Bar-B-Q Pit N54W	55.4' 67.7' 63.2' 98.4'
16/1972	James H. Granger	16041		Boundary	Fnd. 1 1/2" Iron Pipe	8) Wood Fence Post N51E 9) Wood Fence Post S68E 10) U. Pole S41W 11) SE Corner Bar-B-Q Pit N54W	55.4' 67.7' 63.2' 98.4'
19/1979	John L. Snyder JOB NO:32865	13352	L5P162	Boundary	Fnd. 1 1/2" Iron Pipe	8) Wood Fence Post N51E 9) Wood Fence Post S68E 10) U. Pole S41W 11) SE Corner Bar-B-Q Pit N54W	55.4' 67.7' 63.2' 98.4'
10/1979	N.N. Fahrner JOB NO:17141	17620	L5P282	Boundary	Fnd. Iron Pipe	4) SE Cor Hse. N11.5W 10) Power Pole S41W 12) 14" Pear N11E 13) 6" Red Maple N45W	99.2' 63.15' to nail 72.6' 62.2'
1/1986	N.N. Fahrner JOB NO:20593	17620		Boundary	Fnd. Iron Pipe	4) SE Cor Hse. N11.5W 10) Power Pole S41W 12) 14" Pear N11E 13) 6" Red Maple N45W	99.2' 63.15' to nail 72.6' 62.2'
28/1993	Craig Eckfeld JOB NO: 93042	33135		Boundary	Fnd. 1 1/2" Iron Pipe	9) Face Wood Fence Post S68E 11) SE Corner Bar-B-Q Pit N54W 14) 24" Maple N05W 15) 22" Maple N10E 16) SW Corner Barn Foundation N40E 17) U. Pole S45W	67.7' 98.4' 38.41' to nail 39.71' to nail 111.4' 75.88' to nail

APPROVED

DATE 10/23/95

CO. REP. Kx