

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

NOV 02 1999

For corners in

WASHTENAW
(County)

Located In: SHARON TOWNSHIP
Corner Code # _____

SECTION _____

1. Public Land Survey T 3S R 3E M-5
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

5017316
Page: 1 of 1
02/26/1999 02:59P
L-2 P-198
Peggy M. Haines - Washtenaw Co. CORREM

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL V. SCHWIMMER, in a field survey on OCT 28, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

U.S. GOVERNMENT NOTES (1816) SET POST FOR CORNER
CYPRESS 16' S 44°E 50 LINKS (1) (GONE)
CYPRESS 6' S 50°W 30 LINKS (2) (GONE)

WITNESSES FOUND PENCILED INTO THE WASHTENAW COUNTY ROAD COMMISSION GRID BOOK:
S 44°E 33.0' CYPRESS (3) (GONE)
S 50°W 19.8' CYPRESS (4) (GONE)
S 82°W 33.96' W. OAK (5) (GONE)
N 63°E *** CHERRY (6) (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF THIS CORNER REMAINS DUE TO CONSTANT DREDGING AND WIDENING OF AN EXISTING COUNTY DRAIN. I RE-ESTABLISHED THE CORNER BASED UPON A TRAVERSE AND SURVEY PERFORMED BY C. WILSON AND ASSOCIATES IN 1983. THIS SAME SURVEY WAS RELIED UPON BY WASHTENAW ENGINEERING DURING A 1993 SURVEY. BOTH PREVIOUS SURVEYORS HAD USED THE EAST 1/4 CORNER OF SECTION 12 AND AN IRON PIPE FOUND AT THE S.E. CORNER OF THE S.E. 1/4 OF THE S.E. 1/4 TO PUSH A LINE TO M-5 AT AN EQUAL DISTANCE. I SET AN IRON AT THIS POSITION THAT FELL NEAR THE REMAINS OF TWISTED FARM CABLE NORMALLY USED TO STABILIZE AT FENCE LINE CORNER POST.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 NE CORNER OF SECTION 13 SHARON TOWNSHIP
SET 2" IRON WITH REMONUMENTATION CAP
N 50°E 14.45' 18" MAPLE WITH NAIL & REMON. TAG IN S-SIDE
N 75°W 45.70' 30" OAK WITH NAIL & REMON. TAG IN S-SIDE
N 65°W 20.44' 12" MAPLE WITH NAIL & REMON TAG IN S-SIDE
N 35°W 59.83' 16" OAK WITH NAIL & REMON TAG IN S-SIDE

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer
Surveyor's Michigan License No. 29018

Date 12-07-1998

COPY

APPROVED
DATE 12-14-98
CO. REP. HA