

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

For corners in

NOV 02 1999

WASHTENAW
(County)
Located In: SHARON TOWNSHIP Corner Code #
1. Public Land Survey T3S R 3E M-7
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

SECTION

5017318
Page: 1 of 2
02/25/1999 02:59P
Peggy M. Haines - Washtenaw Co. CORREM L-2 P-200
- COPY -
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL V. SCHWIMMER, in a field survey on OCT 28, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. WITNESSES FROM NOTES (1816) SET POST
W. OAK 10° N 60°E 50 LINKS (1) (GONE)
W. OAK 16° S 46°E 29 LINKS (2) (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SURVEYOR OWENS IRON PIPE PER REMAINING WITNESSES, SET 2" X 18" IRON PIPE WITH ALUMINUM REMONUMENTATION CAP OVER THE OWENS IRON.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 N.E. CORNER OF SECTION 24 SHARON TOWNSHIP
SET 2" IRON WITH REMONUMENTATION CAP OVER FOUND 1/2" IRON PIPE (2)
S 10°W 23.18' (MEAS 23.36') 10' CEDAR WITH NAIL & REMON TAG IN W-SIDE (5)
S 40°W 47.14' (MEAS 47.34') 26' HICKORY WITH NAIL & REMON TAG IN S-SIDE (6)
S 80°W 16.80' 7' CEDAR WITH NAIL & REMON TAG IN S-SIDE
S 80°W 31.83' 8' CHERRY WITH NAIL & REMON TAG IN S-SIDE
IRON IS IN N-S FENCELINE



Signed by Paul V. Schwimmer
Surveyor's Michigan License No. 24618

Date 12-07-1998

COPY

APPROVED
DATE 12-14-98
CO. REP. KA

A:

10\26\1976 ACT 74 RECORDED BY SURVEYOR JACK OWENS STATING THAT NONE OF THE ORIGINAL GOVERNMENT WITNESSES REMAIN. HE RESET THE CORNER BY:
SET CORNER BASED UPON THE N-S FENCE LINE AS OCCUPATION AND AT N-S PROPORTIONALTE DISTNACE FROM THE S.W. CORNER OF SECTION 19 NORTH TO E-W DITCH ON NORTH LINE OF SECTION 13 AS BASED UPON 1846 RECORDS OF RESURVEY OF THE TOWNSHIP LINE. DUG FOR EVIDENCE OF ORIGINAL WITNESS TREES) FOUND NONE.

SET 1/2" X 18" IRON ON N-S FENCELINE (3)
2" FORKED R. CEDAR S 15°E 35.01' TO NAIL (4)
2" R. CEDAR S 10°W 23.13' TO NAIL (5)
25" HICKORY S 40°W 47.14' TO NAIL (6)



5017318

Page: 2 of 2

02/25/1999 02:59P

Peggy M. Haines - Washtenaw Co. CORREN L-2 P-201

- COPY -

SURVEY &
REMONUMENTATION

NOV 02 1999

SECTION