

SURVEY &
REMONUMENTATION

MAY 09 1996

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00001 Page 0439*

- Copy -

RECORDED
WASHTENAW COUNTY, MI
MAR 29 1 33 PM '96
REGISTER OF DEEDS
COUNTY CLERK'S OFFICE
- COPY -

For corners in

<u>Washtenaw</u> (county)	Located in:	Corner Code #
1. Public Land Survey	T 3S R 3E	M9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, R.T. Tietsema, in a field survey on May 31, 1995, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

1816	GLO (Fletcher)	Field Notes	Set Original Corner Set post for Corner of Sections 24 & 25 Corner in a small prairie	No witnesses given
------	----------------	-------------	--	--------------------

(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron Pipe
Also found remaining witnesses:

1) Power Pole	S30E	65.93'
2) 3-18" Oak	S85E	67.97'
4) Centerline gravel Kothe Rd	East	15.0'
5) Twin (10", 15") Willow	North	36.03'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap on existing 3/4" Iron Pipe
Set additional accessories:

1) Power Pole	S30E	65.93 to nail & R.T.'
2) 3-18" Oak	S85E	67.97 to nail & R.T.'
4) Centerline gravel Kothe Rd	East	
5) Twin (10", 15") Willow	North	36.03 to nail & R.T.'
6) 8" Locust	S05E	33.35 to nail & R.T.'

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by *R. Tietsema* Date 11 Dec 95
Surveyor's Michigan License No. 20712

-copy-

Section A continued

Date	Name	Lot	Section	Description	Measurements
0/30/1976	Jack N. Owens	20709	L4P188	Set 1/2"x18" Iron Pipe on the West Bank of Road Berm Set corner on the west line of Section 30, T3S, R4E, at the intersection of the extension of the south line from the SW corner Section 24, T3S, R3E, easterly through the S 1/4 corner of Section 24 as best position for the corner.	1) Power Pole S40E 65.50' to nail in N. side 2) Double 14" B. Oak S85E 67.63' to nail N. side 3) Power Pole S40E 65.50' to nail N side 4) Centerline gravel surface Kothe Road East 14.5'
1/10/1984	Paul V. Schwimmer JOB NO:35279	24618	Boundary	Fnd. 1/2" Iron	1) Power Pole S40E 65.50' to nail 2) Twin 14" Oak S85E 67.68' to nail 4) Centerline Grav. RD East 14.5'
1/18/1987	Robert H. Harris	25846	L7P125	Fnd. 3/4" Capped Iron Pipe	1) Power Pole S40E 65.50' to nail in NE side 2) 3-18" Oak S85E 67.68' to nail N/S 5) 6" Oak North 36.18' to nail E/W
1/27/1987	Robert G. Macomber	27453	Boundary	Fnd. 3/4" Capped Iron Pipe	1) Power Pole S40E 65.50' to nail in NE side 2) 3-18" Oak S85E 67.68' to nail N/S 5) 6" Oak North 36.18' to nail E/W

APPROVED
 DATE 10/23/95
 CO. REP. KA