

**SURVEY &  
REMONUMENTATION**

**MAY 09 1996**

**COMMISSION**

Liber **00001** Page **0441** \*

**REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

*copy*

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>3E</u>	<u>M10</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED  
 WASHTENAW COUNTY, MI  
 MAR 29 1 33 PM '96  
 FERGUSON, JAMES  
 COUNTY CLERK / REGISTER  
*copy*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, R.T. Tietsema, in a field survey on May 31, 19 95, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate**

**A. Description of original monument and accessories and/or subsequent restoration:**

1816	GLO (Fletcher)		Fld. Notes	Set Original Corner	1) 12" B. Oak 2) 4" Hickory	North N76E	18 links(11.88' 72 links(49.06'	
				Set 1/2 mile post				
4/10/1984	Paul V. Schwimmer JOB NO: 35279	24618	L7P7	Boundary	Set 3/4" x 18" Iron Pipe on line between the NE Cor and the SE Cor and on Occupation line to the West		3) 14" Cedar 4) 18" Spruce 5) NW Cor. Hse #6501 6) SW Cor Hse #6501 7) 18" Walnut	N60E 33.4 N80E 77.2 N75E 93.6 S80E 93.5 S40 E 44.4

(Continued on back)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" Iron Pipe in center of Kothe Road  
 Also found remaining witnesses:

3) 20" Cedar	N71E	33.10'	
5) NW Corner of House # 6501	N75E	93.6'	
6) SW Corner of House # 6501	S80E	93.5'	
7) 16" Walnut	N21E	80.12'	

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Remonumentation Cap  
 Set additional accessories:

3) 20" Cedar	N71E	33.10'	to nail & R.T.
5) NW Corner of House # 6501	N75E	93.6'	
6) SW Corner of House # 6501	S80E	93.5'	
12) 16" Walnut	N21E	80.12'	to nail & R.T.

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by *R. T. Tietsema* Date 11 DEC. 95  
 Surveyor's Michigan License No. 20712

- Copy -

Section A continued

1/15/1984	Thomas Sutherland JOB NO: 21111	24620	Boundary	Fnd. 1/2" Iron Pipe	8) 58" Oak 9) Pipeline Marker 10) Pipeline Marker 11) Fence Post	S25E South South North	247.19' to nail 108.96' 57.23' 43.35' to nail
1/18/1987	Robert H. Harris	25846	L7P125	Fnd. 1" Capped Iron Pipe	3) 20" Cedar 7) 16" Walnut 12) 14" Walnut	N71E S37E N21E	33.10' 44.53' 80.06'
2/27/1987	Robert G. Macomber JOB NO: 37059	27453	Boundary	Fnd. 1" Capped Iron Pipe	3) 20" Cedar 7) 16" Walnut 12) 14" Walnut	N71E S37E N21E	33.10' 44.53' 80.06'

APPROVED

DATE 10/23/95

CO. REP. K