

MAY 09 1996 COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

- Copy - MAR 29 1 34 PM '96 REGISTERED WASHTEAW COUNTY, MI

For corners in

Table with columns: Washtenaw (county), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, R.T. Tietsema, in a field survey on May 31, 1995, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered. found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: Year, Name, Field Notes, Set Original Corner, Set post Corner of Sections 25 & 36, Found a large stone with small stones around it, Reset with 1 1/2" Iron Pipe, bricks, and stones.

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" Iron Pipe at intersection of Bethel-Church Road and Kothe Road
Also found remaining witnesses:
3) 14" Cedar N41E 53.82' to nail in SE side
17) Power Pole S43E 45.40' to nail in NE side
19) MBT Pole N72W 70.36' to nail N/S
20) Power Pole S69W 78.86' to nail N/S

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap
Set additional accessories:
3) 14" Cedar N41E 53.82' to nail & R.T. in SE side
17) Power Pole S43E 45.40' to nail & R.T. in NE side
19) MBT Pole N72W 70.36' to nail & R.T. N/S
20) Power Pole S69W 78.86' to nail & R.T. N/S

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by [Signature] Date 11 Dec. 95
Surveyor's Michigan License No. 20712

- Copy -

Section A continued

Date	Client	Acres	Section	Boundary	Foundations	Utilities	Measurements
27/1973	M.J.Knowles, Jr Client: W.Eggelston (No Job Number given)	5342		Boundary		No Witnesses given	
3/1974	Allen R. Rentschler	15411	L3P393		Fnd Iron	3) 12" Juniper 6) 20" Walnut 7) Power Pole	N44E 53.86' to nail E. side S75E 102.02' to nail W. side S50E 45.40' to nail NE side
10/1979	N. N. Fahrner JOB NO: 17141	17620	L5P283	Boundary	Fnd. 1 1/2" Iron Pipe Raised with 1" Iron Pipe	3) 10" Juniper 6) 20" Walnut 8) Power Pole 7) Power Pole 9) U. Pole	N43E 53.9' S74W 101.5' N32E 59.6' S42E 45.4' N70W 70.2'
0/1984	Paul V. Schwimmer JOB NO: 35279	24618		Boundary	Fnd. 1 1/2" Iron	3) 10" Juniper 6) 20" Walnut 7) Power Pole 8) Power Pole 9) U. Pole	N43E 53.9' S74W 101.5' S42E 45.4' N32E 59.6' N70W 70.2'
15/1984	Thomas Sutherland JOB NO: 21111	24620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 10" Juniper 6) 20" Walnut 7) Power Pole 8) Power Pole	N43E 53.9' S74W 101.5' S42E 45.4' N32E 59.6'
18/1987	Robert H. Harris	25846	L7P124		Fnd. 1 1/2" Iron Pipe	3) 14" Cedar 7) Power Pole 9) MBT Pole 10) Power Pole	N41E 53.82' to nail in SE side S43E 45.40' to nail in NE side N72W 70.36' to nail N/S S69W 78.86' to nail N/S
27/1987	Robert G. Macomber JOB NO: 37059	27453		Boundary	Fnd. 1 1/2" Iron Pipe	3) 14" Cedar 7) Power Pole 9) MBT Pole 10) Power Pole	N41E 53.82' to nail in SE side S43E 45.40' to nail in NE side N72W 70.36' to nail N/S S69W 78.86' to nail N/S

APPROVED
 DATE 10/23/95
 CO. REP.