

**SURVEY & REMONUMENTATION**

MAY 09 1996

COMMISSION

Liber 00001 Page 0445 R

**REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

- COPY -

RECORDED  
WASHTENAW COUNTY, MI  
MAR 29 1 34 PM '96  
PEGGY H. HAINES  
COUNTY CLERK/REGISTRAR  
- COPY -

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T 3S R 3E	M12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, R.T. Tietsema, in a field survey on May 31, 19 95, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate**

**A. Description of original monument and accessories and/or subsequent restoration:**

1816	GLO (Fletcher)		Fld. Notes	1/2 mile post in small pond.	No bearings given.
Unknown	H.H. Atwell			Found old end post in muck swamp. Set Iron Pipe, stones, and bricks	1) 5" B. Cherry S20W 35.5' 2) 10" B. Cherry S80W 13.6' 3) 4" B. Cherry N87W 66.7'
10/10/1979	N.N. Fahrner JOB NO:17141	17620	LSP283	Boundary 1 1/2" Iron Pipe in Fence running N, S, W	4) RR tie in Fence Post North 2.39' 5) 20" Willow S05W 85.06' to nail 6) 20" Oak S80W 62.13' to nail 7) Multi. Maple N75E 35.92' to nail

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1 1/2" Pinched Iron Pipe in N/S Fence Line  
Also found remaining witness:  
4) RR tie in Fence post North 2.53'

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Repace with 1" Iron Pipe and Remonumentation Cap  
Also found remaining witness:  
4) RR tie in Fence post North 2.53' to nail and R.T.  
8) Multi-Maple N30E 55.80' to nail & R.T.  
9) 24" Oak West 61.22' to nail & R.T.  
10) 14" Locust S30W 31.43' to nail & R.T.

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the original corner.

APPROVED  
DATE 10/23/95  
CO. REP. [Signature]

Signed by [Signature] Date 11 Dec. 95  
Surveyor's Michigan License No. 20712