

MAR 09 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
WASHTENAW COUNTY, MI

JAN 22 8 34 AM '98

For corners in

WASHTENAW (County)	Located in: LODI TOWNSHIP	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>5E</u>	<u>G-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

PEGGY M. HAINES
COUNTY CLERK/REGISTER

- COPY -

- COPY -

Liber **00002** Page **0077 R**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL V. SCHWIMMER, in a field survey on DEC 05, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.D. (1800'S) SET POST
- B. OAK 16° S 77°W 25 LINKS (1) (GONE)
- W. OAK 12° S 53°E 15 LINKS (2) (GONE)

IN THE LATE 1800'S S. PETTIBONE REWITNESSED THE CORNER AS FOLLOWS:
N 02°W 42.9' 24' HICKORY (3) (GONE)
N 09°E 93.1' 14' W. OAK (4) (GONE)
S 62°W 58.7' 8' HICKORY (5) (GONE)

CONT ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND THE 1' BAR FROM THE ABOVE WITNESSES. I RAISED THE POSITION WITH A 1' X 18' IRON PIPE CAPPED WITH AN ALUMINUM REMONUMENTATION CAP. I THEN SURROUNDED THE IRON WITH ROCKS AND STONES.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET REMONUMENTATION CAP OVER 1' IRON USED TO RAISE A FOUND 1' BAR. SURROUNDED THIS IRON WITH 2' TO 3' ROCKS.
- N 25° E 34.79' SET NAIL AND REMON TAG NEAR FD. NAIL IN W. SIDE 12' HICKORY (7)
- N 70° E 50.55' SET NAIL & REMON TAG NEAR FD. NAIL IN S. SIDE 28' HICKORY (6)
- S 50° E 50.26' SET NAIL & REMON TAG NEAR FD. NAIL IN N. SIDE POWER POLE (8)
- S 15° E 52.62' SET NAIL & REMON TAG NEAR FD. NAIL IN W. SIDE 12' CHIN. ELM
- N 20° W 45.95' SET NAIL & REMON TAG NEAR FD. NAIL IN E. SIDE OF 14' HICKORY (13)
- N 40° W 37.24' SET NAIL & TAG NEAR FD. NAIL IN FENCEPOST (12)

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer
Surveyor's Michigan License No. 24618

Date 12-17-97

APPROVED
DATE 12/9/97
CO. REP. KA

- COPY -

SECTION 'A' CONTINUED

IN 1942, W.J. ARMSTRONG WAS AT THIS POSITION WHEN TRYING TO RE-ESTABLISH THE N 1/4 CORNER OF SECTION 33. HIS FIELD NOTES DO NOT GIVE ANY WITNESSES FOR THIS LOCATION.

WASHTENAW ENGINEERING RECORDED AN ACT 74 (LIBER 1, PAGE 331) IN 1971
FOUND 1' IRON BAR

N 70°E 50.6 18' SHAG HICKORY (6) (MEAS 50.55)
N 32°E 34.9 4' HICKORY (7) (MEAS 34.79')
S 53°E 50.0 POWER POLE (8) (MEAS 50.26')
N 38°E 33.7' 4' HICKORY (9) (GONE)
N 23°W 46.8' 8' HICKORY (10) (MEAS 45.95)

MR. JAMES FISH RECOVERED THIS POSITION IN 1973 WITH THESE WITNESSES:

S 40°E 49.72 NAIL IN POWER POLE (8)
N 35°E 34.88 NAIL IN FENCE POST (11) (FALLEN DOWN)
N 30°W 37.28 NAIL IN FENCE POST (12)

WASHTENAW ENGINEERING RECORDED AN ACT 74 (LIBER 5, PAGE 151) IN 1978
FOUND 1' IRON BAR WITH THE SAME WITNESSES AS ABOVE

IN 1979 ATWELL-HICKS, INC. RECORDED WITNESSES TO A FOUND 1' BAR IN THEIR WITNESS GRID BOOK:

N 70°E 50.50 FD. NAIL IN S. FACE OF 18' SHAG HICKORY (6) (MEAS 50.55)
N 15°E 34.89 FD. NAIL IN N.W FACE OF 10' HICKORY (7) (MEAS 34.79')
S 53°E 49.96 FD. NAIL IN N FACE OF POWER POLE (8) (MEAS 50.26')
SOUTH 33.01 FOUND IRON

WASHTENAW ENGINEERING RECORDED THIS CORNER ON AN ACT 132 SURVEY (LIBER 1837, PAGE 854) IN 1982

FOUND 1' BAR

N 70°E 50.6 18' HICKORY (6)
S 53°E 50.0 POWER POLE (8)
N 30°W 45.85 NAIL IN 12' HICKORY (13)
N 15°E 34.94 NAIL IN 6' HICKORY (7)

C. WILSON & ASSOCIATES, INC. RECOVERED THE CORNER IN 1988 ON AN ACT 132 SURVEY.

FOUND 1' BAR

N 70°E 50.6 18' HICKORY (6)
S 53°E 50.0 POWER POLE (8)
N 30°W 45.85 12' HICKORY (13)
N 15°E 34.94 6' HICKORY (7)

70-4.-31