

MAY - 1 1995

COMMISSION

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

1 PAGE 225 Rm

- Copy -

For corners in

Washtenaw
(County)

Located In:

Corner Code ##

1. Public Land Survey	T <u>3S</u> R <u>5E</u>	<u>I-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- COPY -
 PEGGY M. HAINES
 COUNTY CLERK/REGISTER
 Dec 1 11 42 AM '94
 WASHTEENAW COUNTY, MI
 RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth R. Coleman in a field survey on 6-29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 See back of sheet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1 1/2" iron pipe 12-14-93
 See back of sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Found 1 1/2" iron pipe 0.25' below gravel surface
 3) N 7° E 33.25 36" Walnut, RT, nail
 4) N 10° E 23.85 34" Oak, RT, nail
 7) South 72.19 P. pole, RT, nail
 8) N 35° W 139.48 SE corner conc. foundation of house #4520



Signed by Kenneth R. Coleman Date 9/19/94
 Surveyor's Michigan License No. 37271

1

- Copy -

I-9 Witness Summary

6-21-1819 J. Wampler D.S.
 Set post corner Section 22, 23, 26 & 27
 1) B.O 27 N 14W 266
 2) No other

Page 261

9-7-40 W.J. Armstrong
 Found Stone Monument, triangular in cross section, left stone in place and put broken bricks and some pieces of iron around it. Set 1 1/2" x 12" iron pipe on top of stone
 3) 18" Walnut N7°E 33.0
 4) 12" S.W. Oak N10-1/2E 23.8
 5) 36" Elm S72°E 82.4
 6) 30" Maple S66-1/2°W 38.0

Page 94 W.C.R.C

1-20-78 Allen R. Rentschler
 Found 1 1/2" Iron Pipe
 3) 27" Walnut, N 7 E, 33.0'
 4) 24" Oak, N 10 E, 23.8'
 7) Telephone pole, South, 72.3'
 8) SE Cor. House, N 35 W, 139.7'

Liber 4, Page 398, W.C.R.

12-14-93 Atwell-Hicks, Inc.
 Found 1-1/2" iron pipe
 3) 27" Walnut N7°E 33.0'
 4) 24" Oak N10°E 23.8'
 7) Tele. Pole South, 72.3'
 8) S E Cor. of House N35°W 139.7'

APPROVED
 DATE 2/28/94
 SO. REP. HA

2