

MAY - 1 1995

COMMISSION

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
WASHTENAW COUNTY, MI

JAN 10 9 43 AM '95

PEGGY M. HAINES
COUNTY CLERK/REGISTER

- COPY -

For corners in

Washtenaw (County) Located In: Corner Code #/

1. Public Land Survey	T <u>3S</u> R <u>5E</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 263 *RM*
- COPY -
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kenneth R. Coleman in a field survey on 6-29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
See back of sheet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1 1/2" iron pipe 12-14-93
See back of sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found 1 1/2" iron pipe 0.8' below surface. Set RT on top with PK nail through RL 37271 cap.

6) N 55° W 56.29	24" Walnut, RT, nail
9) South 33.26	P. pole, RT, nail
10) North 32.68	P. pole, RT, nail
11) S 75° W 83.57	12" Hickory, RT, nail



Signed by Kenneth R. Coleman Date 9/19/94
Surveyor's Michigan License No. 37271

K-12 Witness Summary

LIBER

1 PAGE 264 RM

Page 258

- Copy -

6-14-1819 J. Wampler D.S.

Set 1/2 mile post

- 1) W.O. 5 S5E 39
- 2) D.O. 34 S63W 30

4-1-38

W. J. Armstrong

W.C.R.C. Grid Book, Page 20

Found old wood stake and stone. Set 1 1/2" x 40" iron pipe, bricks, stones and a dog.

- 3) 32" Elm, N 50 E, 46.8'
- 4) 12" B. Cherry, N 69 E, 80.5'
- 5) 5" B. Walnut, S 72 E, 67.2'
- 6) 12" B. Walnut, N 63 W, 56.4'
- 7) 14" B. Walnut, N 34 W, 29.9'

1-8-44

AHI Field Book 518, Page 63

Found Post

- 3) 32" Elm N 51 E 46.8'
- 4) 12" B. Cherry N 69 E 80.5'
- 5) 5" B. Walnut S 72 E 67.2'
- 6) 12" B. Walnut N 63 W 56.4'
- 7) 14" B. Walnut N 34 W 29.9'

9-75 Control Survey Associates, Inc. Survey-Job # 3S5E36-75-51. Survey indicates found marker (type unspecified).

- 7) 18" Walnut, N 30 W, 29.85'
- 8) 16" Shagbark, N 75 E, 93.84'
- 9) D.E. Pole, S 2 W, 31.19'

5-17-77

Norman N. Fahrner

Liber 4, Page 275,

W.C.R.

Found iron pipe.

- 6) 18" B. Walnut, N 63 W, 56.4'
- 7) 18" B. Walnut, N 34 W, 29.9'
- 9) Power Pole, South, 31.2'
- 10) Telephone pole, North, 32.3'

5-30-79

Atwell-Hicks, Inc.

Survey-Job #33114

Survey indicates found 1 1/2" Iron Pipe.

- 6) 18" B. Walnut, N 63 W, 56.4'
- 7) 18" B. Walnut, N 34 W, 29.9'
- 9) Power pole, South, 31.2'
- 10) Telephone pole, North, 32.3'

12-14-93

Atwell-Hicks, Inc.

Found 1-1/2" iron pipe with P.K. nail in center

- 6) 18" B. Walnut, N 63°W 56.4'
- 7) 18" B. Walnut, N 34°W 29.9'
- 9) Power Pole North 32.3'
- 10) Power Pole South 31.2'

APPROVED

DATE 2/15/94

CO. REP. KA