

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

COMMISSION

For corners in

COPY

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED
WASHTENAW COUNTY, MI

JAN 10 9 43 AM '95

PEGGY M. HAINES
COUNTY CLERK/REGISTER

- COPY -

Washtenaw
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>3S</u> R <u>5E</u> | <u>L-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

LIBER 1 PAGE 267 RM
- COPY -
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kenneth R. Coleman in a field survey on July 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
See back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 3/4" iron pipe 7-31-91
See back of sheet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found 3/4" iron pipe w/W.C.R.C. cap. Found boat spike 10" deep along N. side pipe.
Set mon. box over pipe.
10) N63°W 63.70 14" Apple, RT
11) S47°E 82.14 P. Pole, RT
13) S 9°W 85.02 8" Twin Maulberry, RT
14) S56°W 83.14 P. Pole, RT



Signed by Kenneth R. Coleman Date 9/19/94
Surveyor's Michigan License No. 37271

L-9 Witness Summary

LIBER 1 PAGE 268 RM
- Copy -

6-21-1819 GLO J. Wampler D.S.
Set 1/4 S Post at av. D.
1) B.O. 20 N82W 3.50
No other

Page 258

3-11-35 W.J. Armstrong W.C.R.C. Grid Book, P, 14
Found a large stone with a large notch cut in top of it. Under this was an old wood stake. Reset with iron pipe, stones and bricks.

- 2) 1" Maple, N 36 E, 22.7'
- 3) 24" Maple, N 74 E, 54.8'
- 4) 3" Y. Oak, S 61/2 W, 27.9'
- 5) 24" Maple, N 82 w, 138.0'
- 6) 1" Maple, N 48 W, 28.3'
- 7) 2 R. of W. pipes.

6-10-80 Robert A. Campbell Jr. Liber 6, Page 246
Found badly bent 1 1/2" iron pipe and brick. Pulled 1 1/2" iron pipe and reset with 3/4"x18" iron pipe and plastic cap, in hole where 1 1/2" iron pipe went straight into ground.

- 3) 32" Maple, N 75 E, 54.99'-Found nail on S side
- 5) -Found 25" stump N 81 W, 137.8'
- 7) 1" iron pipe S4°W 33.00'
- 8) Utility pole, S 22 W, 91.58', set nail E side
- 9) Utility pole, S 61 W, 44.17', set nail SE side
- 10) 13" Apple, N 67 W, 63.63', set nail S side

5-5-82 Norman Fahrner Liber 6, Page 228
Found 3/4" Iron Pipe.

- 7) 2 R/W Irons
- 9) Power pole, S 50 W, 44.22' to nail
- 10) 6" Apple, N 65 W, 63.64' to nail
- 11) 6" Maple, South, 62.92' to nail

12-15-83 Atwell-Hicks, Inc Liber 2392, Page 316
Found 3/4" Iron Pipe.

- 7) 2 R/W Irons
- 9) Power pole, S 50 W, 44.22', nail
- 10) 6" apple, N 65 W, 63.64' nail
- 11) 6" Maple, South, 62.92' nail

7-31-91 Atwell-Hicks, Inc. Liber 2531, Page 336
Found 3/4" Iron Pipe, 9.6' N of C/L stripe.

- 10) S face of 8" Apple, N 63 W, 63.8' nail
- 12) NE face of power pole, S 47 E, 82.3', nail
- 13) W face of 8" twin Mulberry, S 05 W, 85.3', nail
- 14) Power pole, S 56 W, 83.4' nail

12-14-93 Atwell-Hicks, Inc.
Found 3/4" iron pipe

- 7) 2 R/W Pipes
- 10) 13" apple N63°W 63.8'
- 12) Nail NE face P. Pole, S47E, 82.3'
- 13) Nail W. Face of 8" twin Mulberry, S9°W, 85.3'
- 14) Nail P. Pole S56W, 83.4'

APPROVED
DATE 1/11/94
CO. REP. KA