

SURVEY & REMONUMENTATION

NOV 02 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

WASHTENAW
(County)

Located in: T 3S R 6E Corner Code # A-9

1. Public Land Survey T _____ R _____ CC
PITTSFIELD TWP T _____ R _____

2. Property controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

5017281
Page: 1 of 2
02/25/1999 02:59P
L-2 P-129

Peggy M. Haines - Washtenaw Co. CORREM

COPY

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, LORI E. BEYER, in a field survey on MARCH 24, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NW CLOSING CORNER SECTION 30 AS MONUMENTED

- A. Description of original monument and accessories and/or subsequent restoration:
- C.S. WOODARD - 1887
CORNER IDENTIFIED AND REESTABLISHED
- | | | |
|----------------|---------|---------------|
| 20" YELLOW OAK | S 02° E | 2.78 (183.5") |
| 12" BURR OAK | S 63° E | 1.06 (66.4') |
- SET STAKE, TILE AND STONES

Continued on Back

- B. Description of corner evidence and/or method applied in restoring or reestablishing corner:
- FOUND 3/4" IRON PIPE INSIDE 1 1/2" IRON PIPE 6" ABOVE GROUND ON N-S TREE LINE. PIPE IS 150' NORTH OF CL OF TEXTILE ROAD AND 1000' WEST OF MAPLE ROAD. PLACED ALUMINUM REMON CAP OVER 3/4" IRON PIPE.
- FOUND FIVE (5) REMAINING WITNESSES.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 3/4" IRON PIPE INSIDE 1 1/2" IRON PIPE WITH ALUMINUM REMON CAP 6" ABOVE GROUND ON N-S TREE LINE 150' NORTH OF CL OF TEXTILE ROAD AND 1000' WEST OF MAPLE ROAD.

(1) 46" OAK	S 02° W	184.75'	FOUND NAIL/WASHER E. SIDE
(3) 36" SWAMP WHITE OAK	S 57° W	231.56'	SET NAIL/TAG SE SIDE
(4) SE COR LODI TWP	SOUTH	148.13'	3/4" IRON PIPE IN MON. BOX
(6) 42" MAPLE	S 06° W	59.29'	SET NAIL/TAG WEST SIDE
(7) 20" TRI ELM	S 02° W	21.23'	SET NAIL/TAG WEST SIDE
(9) 4" TW. ASH	N 26° E	20.98'	SET NAIL/TAG EAST SIDE
(10) 1/2" IRON PIPE	S 01° E	181.01'	

THIS CORNER IS NOT COMMON WITH M-9 OF LODI TWP.
A-9 IS 1.9' WEST OF THE LINE BETWEEN M-9 AND M-8, LODI TWP
A-9 IS 148.1' NORTH OF M-9 LODI TWP



AFTER CAREFUL EXAMINATION OF RECORD DOCUMENTATION AND FIELD OBSERVATIONS, I BELIEVE THIS POINT SHOULD BE ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS RATIFIED BY THE PEER REVIEW COMMITTEE IN NOVEMBER, 1998.

Signed by Lori E. Beyer Date Dec 23, 1998
Surveyor's Michigan License No. 41092

APPROVED
DATE 11-5-98
CO. REP. PA

COPY

**SURVEY &
REMONUMENTATION**

NOV 02 1999

SECTION

A-9

5017281
Page: 2 of 2
02/25/1999 02:59P
L-2 P-130
COPY

Continued from Section A:

W.J. Armstrong – RLS 2444 - August 1934 - Washtenaw County Road Commission Grid Book
Found Woodard's tile, stake and stones. Reset with 1 1/2" x 40" Iron Pipe. Left tile in place and put stones and brick around it.

- | | | |
|----------------------|-------------|--------|
| 1) 40" Y. Oak | S 21 1/2° E | 183.5' |
| 2) 15" B. Cherry | S 34° W | 167.0' |
| 3) 36" S.W. Oak | S 60° W | 232.3' |
| 4) SE Co Sec 24 Lodi | South | 147.6' |

Robert J. Jagow – RLS 6998 – September 1972 – L.C.R.C. Liber 2 Page 389

Found 1 1/2" Iron Pipe with tube inside

- | | | |
|-----------------------|-------------|--------|
| 1) 40" Yellow Oak | S 21 1/2° E | 184.2' |
| 3) 36" S.W. Oak | S 60° W | 232.3' |
| 5) 12" Maple | North | 21.1' |
| 6) 14" Maple | South | 59.7' |
| 4) SE Cor Sec 24 Lodi | South | 147.6' |

Norman N. Fahmer – RLS 17620 – April 1978 – L.C.R.C. Liber 5 Page 44

Found 1 1/2" Iron Pipe

- | | | |
|-----------------|-------------|------------------------------|
| 1) 40" Y. Oak | S 02 1/2° E | 183.5' (Bearing may be typo) |
| 7) 6" Tri Elm | S 05° E | 21.25' Nail |
| 8) Maple Clump | N 02° W | 59.35' Nail |
| 5) 12" S. Maple | N 02° W | 20.75' Nail |

Urban Engineering – September 1980 – Survey Job No. 6020

Found 2" Iron Pipe

- | | | |
|-----------------------|-------|---------------------|
| 5) 16" Maple | N'y | 21.02' Nail E. side |
| 7) 8" Elm | SSE'y | 21.24' Nail E. side |
| 4) SE Cor Sec 24 Lodi | South | 147.94' |

Norman N. Fahmer – RLS 17620 – April 1978 – L.C.R.C. Liber 5 Page 44

Found 1 1/2" Iron Pipe

- | | | |
|-----------------|-------------|------------------------------|
| 1) 40" Y. Oak | S 02 1/2° E | 183.5' (Bearing may be typo) |
| 7) 6" Tri Elm | S 05° E | 21.25' Nail |
| 8) Maple Clump | N 02° W | 59.35' Nail |
| 5) 12" S. Maple | N 02° W | 20.75' Nail |

Charles C. Wilson – RLS 13604 – 1990 – "McCormick Place" – Liber 27 of Plats, Pages 97-101

Y9100