

MAR 09 1998

RECORDED
WASHTENAW COUNTY, MI

JAN 22 8 31 AM '98

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PEGGY M. HAINES
COUNTY CLERK/REGISTER

For corners in

WASHTENAW (County)	Locoted In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>6E</u>	<u>G-11</u>
PITTSFIELD	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

- COPY -

- COPY -

Liber **00002** Page **0045** *RM*
Register of Deeds Stamp & File Number


I, LORI E. BEYER, in a field survey on NOVEMBER 26, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. -- 1819 FIELD NOTES
SET POST
18" W.O. N 08° W 165.00'
6" HICKORY N 74 1/2° E 95.04'



Continued on Back

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE ON TOP OF 1 1/2" IRON PIPE FLUSH WITH GROUND APPRX. 4' W. OF EDGE OF WARNER RD. TOP OF 1 1/2" IRON PIPE IS MUSHROOMED AND HAS A 1" IRON DRIVEN INSIDE OF IT. SET ALUMINUM REMONUMENTATION CAP STAMPED WITH 'ALNM - #41092' ONTO 1" IRON PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1 1/2" IRON PIPE FLUSH WITH SURFACE WITH 1" IRON DRIVEN INTO IT. SET ALUMINUM REMONUMENTATION CAP ON 1" IRON AND MARKED CAP WITH 'ALNM - #41092'.
(1) 27" HICKORY N 10° E 76.86' SET NAIL & FLASHER E. SIDE
(4) 27" HICKORY S 05° E 133.73' SET NAIL & FLASHER W. SIDE
(5) 22" HICKORY S 15° W 59.50' SET NAIL & FLASHER E. SIDE
(6) 24" HICKORY S 34° W 25.13' SET NAIL & FLASHER E. SIDE
(10) POWER POLE WEST 20.83' FD PK NAIL & FLASHER N. SIDE

APPROVED
DATE 12/2/97
CO. REP. [Signature]

AFTER CAREFUL EXAMINATION OF RECORD DOCUMENTATION AND FIELD OBSERVATIONS, I BELIEVE THIS POINT SHOULD BE ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Lori E. Beyer
Surveyor's Michigan License No. 41092

Date Dec 08, 1997

W.J. Armstrong - September 1934

Washtenaw County Road Commission - Grid Book

Found short piece of Iron Pipe, Stake and Tile, also stones and bricks.
Drove 1" X 40" Iron Pipe into the tile and replaced the stones and bricks around it.

- COPY -

(1) 36" W. OAK	N 25 1/2° W	141.9'
(2) 4" HICKORY	S 26° E	72.8'
(3) 10" HICKORY	S 22° E	110.2'
(4) CENTER OF WELL	N 85° W	124.4'
(5) 10" HICKORY	N 89° W	196.4'
(6) 16" HICKORY	N 56 1/2° W	219.9'
(7) S.END W. HDWL	N 15° W	61.5'
(8) S.END E. HDWL	N 15° E	62.7'
(9) CL OF US-112 PVMT		164.1'
(10) 3 R.O.W. PIPES		

Howard H. Taft, RLS #12032 - May 1973

Washtenaw County Records P.A. 132 Certificate - Liber 1439 Page 980

Found Iron Pipe

(2) 12" HICKORY	S 26° E	72.8'
(3) 16" HICKORY	S 22° E	110.2'
(6) 16" HICKORY	N 89° W	196.4'
(7) S.END W.HDWL	N 15° W	61.5'
(8) S.END E.HDWL	N 15° E	62.7'

Douglas W. Hooth, RLS #7966 - MDSH - May 1976

Washtenaw County Records LCRC - Liber 4 Page 143

Found 3/4" Iron Pipe with A.H.R.S. tag #12032

(11) CHISELED X IN N.END HDWL	N 15° E	68.68'
(12) CHISELED X IN N.END HDWL	N 20° W	67.57'
(2) 15" HICKORY	S 35° E	72.80'
(9) CL OF EXISTING US-12	NORTH	163.16'

MDOT Road Plans for US-12 - 1978

Found 3/4" Iron Pipe with A.H.R.S. Tag #12032

(12) 'X' N. END CONC. HDWL	N 20° W	67.57'
(11) 'X' N. END CONC. HDWL	N 15° E	68.68'
(2) 15" HICKORY	S 35° E	72.80'
(13) CL OF EX US-12	NORTH	77.35'

Paul V. Schwimmer, RLS #24618 - November 1990

Ayres, Lewis, Norris & May - Field Book

Found Shipspike in CL of Warner Road

(14) PK/FLASHER IN U. POLE	S 45° W	41.75'
(15) TOP CL OF F. HYDRANT	S 35° E	74.40'
(16) EDGE CONC. US-12	NORTH	51.25'
(17) 1" PIPE/CAP A.H.R.S. #27453	S 05° W	108.42'