

MAR 09 1998

SECTION

RECORDED  
WASHTENAW COUNTY, MI

JAN 22 8 31 AM '98

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 000070

PEGGY W. HAINES  
CLERK/REGISTER

For corners in

WASHTENAW (County)	Located In:	Corner Code #
1. Public Land Survey PITTSFIELD	T <u>3S</u> R <u>6E</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plot _____		
5. Private Claims _____		

- COPY -

- COPY -

Liber 00002 Page 0047 RM  
Register of Deeds Stamp & File Number

I, LORI E. BEYER, in a field survey on NOVEMBER 26, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. - 1819 FIELD NOTES  
SET POST  
9" HICKORY N 79° E 36.3'  
5" B.O. N 66° W 41.6'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Continued on Back

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE BEGINNING 8" BELOW GRAVEL ROAD SURFACE BETWEEN HOUSE #7500 AND HOUSE #7536 CREW WAS UNABLE TO DIG TO ARMSTRONG IRON ON THAT DAY. BASED ON THE RECORDS OF THE PERPETUATION OF ARMSTRONG'S IRON WITNESSES, AND AGREEMENT WITH RECORD DISTANCES, I ACCEPTED THIS MONUMENT AS THE CORRECT LOCATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 3/4" IRON PIPE 8" BELOW GRAVEL. PLACED ALUMINUM REMONUMENTATION CAP STAMPED 'ALNM - #41092' ON TOP OF 3/4" IRON PIPE.

(2) 30" R. OAK	S 26° W	107.95'	SET NAIL & FLASHER
(4) 16" TRI-OAK	S 31° W	76.85'	SET NAIL & FLASHER
(5) UTILITY POLE	S 86° W	33.98'	FD NAIL N. SIDE
(8) SW'LY CORNER HOUSE	N 73° E	157.3'	
(9) CTR 3" STEEL F. POST	S 81° E	34.7'	
(6) SE'LY CORNER HOUSE	N 52° W	118.0'	

APPROVED  
DATE 12/2/97  
CO. REP. [Signature]

AFTER CAREFUL EXAMINATION OF RECORD DOCUMENTATION AND FIELD OBSERVATIONS, I BELIEVE THIS POINT SHOULD BE ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Lori E. Beyer

Date Dec 8, 1997

Surveyor's Michigan License No. 41092

## Paragraph A Continued:

W.J. Armstrong -- September 1934  
 Washtenaw Co. Road Commission -- Grid Books  
 Found Woodard's Stake, Stone's, and Iron Ring. Reset with a 1 1/2" X 36"  
 Iron Pipe with stones and bricks around it.

(1) 14" HICKORY	N 05° E	77.4'
(2) 4" HICKORY	S 51° E	33.1'
(3) 6" HICKORY	S 42° E	34.8'(MARKED)
(4) 14" HICKORY	S 07° E	133.0'
(5) 5" HICKORY	S 16° W	59.3'
(6) 8" HICKORY	S 36° W	25.2'(MARKED)
(7) 2 R.O.W. PIPES		

## Author/Date Unknown

Washtenaw Co. Road Commission -- Grid Book -- Added Notes  
 (9) 5" APPLE N 70° E 89.2'

## Allen R. Rentschler, RLS #15411 -- July 1971

Washtenaw Co. Records -- LCRC Liber 1 Page 173, P.A. 132 Certificate, Liber 1369 Page 381

Found 1" Iron Pipe

(1) 20" Hickory	N 05° E	77.4'
(8) T. POLE	E'LY	32.0'
(6) 18" HICKORY	S 36° W	25.2'

## Allen R. Rentschler, RLS #15411 -- November 1975

Washtenaw Co. Records -- P.A. 132 Certificate, Liber 1533 Page 426, Liber 1539 Page 224,

Liber 1539 Page 222

Found 2 1/2" Iron Pipe

(1) 24" HICKORY	N 05° E	77.0'
(5) 15" HICKORY	S 16° W	60.0'
(10) POWER POLE	N 85° W	21.1'
(6) 15" HICKORY	S 36° W	25.2'

## Murray J. Knowles, RLS #5342 -- July 1977

Washtenaw Co. Records -- P.A. 132 Certificate, L. 1604 Pg. 390, L. 1605 Pg. 896, L. 1606 Pg. 849

Section corner shown as part of a boundary survey, but no indication of found or set and no witnesses listed.

## Allen R. Rentschler, RLS #15411 -- April 1978

Washtenaw Co. Records -- P.A. 132 Certificate, L. 1655 Pgs. 764,765

Found 2 1/2" Iron Pipe

(1) 24" HICKORY	N 05° E	77.0'
(5) 15" HICKORY	S 16° W	60.0'
(10) POWER POLE	N 85° W	21.1'
(6) 15" HICKORY	S 36° W	25.2'