

MAR 09 1998

RECORDED WASHTENAW COUNTY, MI

SECTION

JAN 22 8 31 AM '98

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

PEGGY R. HAINES COUNTY CLERK/REGISTER

For corners in

Table with columns: WASHTEAW (County), Located In: (T, R), Corner Code #. Includes entries for Public Land Survey PITTSFIELD and Property controlling in Section.

- COPY -

- COPY -

Liber 00002 Page 0051 R Register of Deeds Stamp & File Number

I, LORI E. BEYER, in a field survey on NOVEMBER 26, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

Grid table with columns A-L and rows 2-13, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. - 1819 FIELD NOTES SET POST 5" TAMARACK S 80° W 11.88' 6" TAMARACK S 04° E 11.22'



Continued on Back

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

COULD NOT FIND MAGNETIC PULL AT WITNESS INTERSECTION. BY MEASURING RECORD DISTANCES AND ANGLES FROM G-9, I-9 AND REMAINING WITNESSES, MARKED POINT THEN DUG APPRX. 3.5' AND FOUND BRICKS INTERLOCKED TO FORM A 2 1/2" HOLE IN THE CENTER. FOUND REMNANTS OF WOOD INSIDE THE CENTER OF THE HOLE. CENTER OF HOLE IS 0.10' EAST AND 0.22' NORTH OF WITNESS LOCATION AS MARKED FROM PREVIOUS RECORD POSITION. SET 3/4" X 36" IRON PIPE IN CENTER OF BRICKS AND HOLE PLACED ALUMINUM REMONUMENTATION CAP STAMPED 'ALNM - #41092' ON TOP OF IRON.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 36" IRON PIPE IN CENTER OF FOUND BRICKS. PLACED ALUMINUM REMONUMENTATION CAP STAMPED 'ALNM - #41092' ONN TOP OF 3/4" IRON PIPE.

Table listing monument details: (6) CONC. ROW POST SOUTH 32.70' FD NAIL TOP CTR, (7) CROSS ROAD SIGN N 10° W 18.6', (10) 10" TW. MAPLE N 30° E 36.89' FD NAIL W. SIDE, (12) 14" MAPLE N 72° W 94.98' SET MAG NAIL & FLASHER, (13) 1/2" IRON BAR N 01° E 32.68', (6A) CONC. ROW POST N 42° W 46.43' FD NAIL TOP CTR, (14) 30" OAK S 68° W 144.39' SET MAG NAIL & FLASHER N. SIDE

APPROVED DATE 12/2/97 CO. REP. KA

AFTER CAREFUL EXAMINATION OF RECORD DOCUMENTATION AND FIELD OBSERVATIONS, I BELIEVE THIS POINT SHOULD BE ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Lori E. Beyer

Date Dec 8, 1997

Surveyor's Michigan License No. 41092

- COPY -

Paragraph A Continued:

W.J. Armstrong - November 1933  
 Washtenaw County Road Commission - Grid Book  
 Found wood stake, brick, and stones. Reset with a 1 1/2" x 46"  
 Iron Pipe with stones and brick.

- (1) 10" ELM N 57 1/2° E 28.65'
- (2) 12" ELM N 79° E 55.4'
- (3) 5" S.W. OAK S 15 1/2° W 27.4'
- (4) 10" ELM N 78 1/2° W 54.1'
- (5) 4" ELM N 75° W 44.75'
- (6) 3 CONC. R.O.W. POSTS

Norman N. Fahrner, RLS #17620 - November 1971  
 Washtenaw Co. Records L.C.R.C. - Liber 1 Page 497, and  
 Washtenaw Co. Records P.A. 132 - Certificate Liber 1386 Page 672  
 Found 1 1/2" Iron Pipe

- (3) 12" OAK S 15 1/2° W 27.4'
- (6) CONC. ROW POST S'LY 32.5'
- (7) CROSS ROAD SIGN POST N 10° W 18.7'

Norman N. Fahrner, RLS #17620 - August 1978  
 Washtenaw Co. Records P.A. 132 - Certificate Liber 1713 Page 694  
 Found 1 1/2" Iron Pipe

- (3) 12" OAK S 15 1/2° W 27.4'
- (6) CONC. ROW POST S'LY 32.5'
- (7) CROSS ROAD SIGN POST N 10° W 18.7'

Charles C. Wilson, RLS #13604 - May 1974  
 Washtenaw Co. Records L.C.R.C. - Liber 4 Page 115  
 Found 1/2" Iron Pipe

- (3) STUMP S 15 1/2° W 27.4'
- (6) CONC. ROW POST S'LY 32.5'
- (7) CROSS ROAD SIGN POST N 10° W 18.7'
- (8) 6" ASH N 10° W 32.5'

D. Tietsma, RLS #20712 - October 1980  
 Ayres, Lewis, Norris & May Field Book  
 Found Iron Pipe

- (9) 6" MAPLE N 10° E 40.0'
- (7) 'T' SIGN THOMAS RD N 05° W 18.3'
- (6) CONC. ROW POST S'LY 32.5'

Robert A. Campbell, Jr., RLS #13028 - July 1982  
 Washtenaw County Records - L.C.R.C. Liber 6 Page 240  
 Found 3/4" Iron Pipe driven into 1 1/2" Iron Pipe

- (6) CONC. ROW POST SOUTH 32.45'
- (7) CROSS RD SIGN POST N 10° W 18.8'
- (10) 8" TWIN MAPLE N 31° E 37.34' FD NAIL E. SIDE
- (11) CLUMP 2"-4" MAPLES N 60° W 58.88' SET NAIL E. SIDE

Paul V. Schwimmer, RLS #24618 - September 1986  
 Washtenaw County Road Commission Field Book  
 Monument not described.

- (6) CONC. ROW POST SOUTH 32.45'
- (7) CROSS RD SIGN POST N 10° W 18.7'
- (10) 10" TWIN MAPLE N 30° E 37.59' SET NAIL
- (12) 12" MAPLE N 72° W 95.13' SET NAIL
- (3) 6" STUMP N 10° W 32.5'

Kevin Anderson, PS #37269 - April 1991  
 Washtenaw County Road Commission Field Book  
 Found Iron Pipe (not described)

- (6) CONC. ROW POST SOUTH 32.40'
- (7) CROSS RD SIGN POST N 10° W 18.7'
- (10) 10" TWIN MAPLE N 30° E 37.61' FD NAIL
- (11) 2"-4" CLUMP MAPLES N 60° W 58.59'
- N 10° W 32.5'