

MAR 09 1998

RECORDED WASHTEENAW COUNTY, MI

JAN 22 8 31 AM '98

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

PEGGY M. HAINES  
COUNTY CLERK REGISTER

- COPY -

- COPY -

Liber 00002 Page 0055 RM  
Register of Deeds Stamp & File Number

For corners in

WASHTEENAW (County)	Located In:	Corner Code #
1. Public Land Survey PITTSFIELD	T 3S R 6E	H-13
	T R	
	T R	
	T R	
2. Property controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, LORI E. BEYER, in a field survey on NOVEMBER 26, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. - 1819 FIELD NOTES  
SET POST  
20" W.O. N 81° W 36.30'  
20" LYNN S 27° W 53.46'

Continued on Back

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE WITH W.C.R.C. CAP #13028 IN MONUMENT BOX AT PAVEMENT SURFACE. BASED ON NOTES BY R. CAMPBELL, ACCEPTED AS CORNER. PLACED ALUMINUM REMONUMENTATION CAP STAMPED 'ALNM #41092' ON TOP OF 3/4" IRON PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 3/4" IRON PIPE IN MONUMENT BOX AT PAVEMENT SURFACE. PLACED ALUMINUM REMONUMENTATION CAP STAMPED '#41092' ON TOP OF 3/4" IRON PIPE.

- (7) POWER POLE N 78° E 148.83' SET MAG NAIL S. SIDE
- (8) POWER POLE N 78° W 162.49' SET MAG NAIL S. SIDE
- (9) 29" APPLE N 58° W 358.8' TO CTR
- (10) 36" PEAR N 03° E 400.6' TO CTR
- (11) TEL. RISER S 82° W 134.32' TO CTR
- (13) S. LEG HI-TENS. TOWER N 28° W 613.0'

APPROVED  
DATE 12/2/97  
CO. REP. KA

AFTER CAREFUL EXAMINATION OF RECORD DOCUMENTATION AND FIELD OBSERVATIONS, I BELIEVE THIS POINT SHOULD BE ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Lori E. Beyer Date Dec 8 1997  
Surveyor's Michigan License No. 41092

- COPY -

## Paragraph A Continued:

Pester, Barnes - November 1932  
Washtenaw County Road Commission - Grid Book  
State Monument

- |                                       |       |       |
|---------------------------------------|-------|-------|
| (1) E. POLE                           | N'LY  | 45.5' |
| (2) T. POLE                           | SW'LY | 38.0' |
| (3) 3 FEET EAST OF RANGE ON N-S FENCE |       |       |
| (4) 3 ROW POSTS                       |       |       |

Norman N. Fahrner, RLS #17620 - November 1971  
Washtenaw Co. Records L.C.R.C. - Liber 1 Page 691, and  
Washtenaw Co. Records P.A. 132 - Certificate Liber 1461 Page 744  
Found Steel Monument

- |             |         |        |
|-------------|---------|--------|
| (5) T. POLE | S 60° E | 74.6'  |
| (6) T. POLE | S 75° W | 87.0'  |
| (7) P. POLE | N 84° E | 149.2' |

Robert Roskelly, RLS #18663 - January 1979  
P.A. 132 - Certificate Not Recorded  
Found 6" Steel Monument

- |              |         |         |      |
|--------------|---------|---------|------|
| (7) DE POLE  | N 70° E | 149.00' | NAIL |
| (5) MBT POLE | S 70° E | 74.55'  | NAIL |
| (6) MBT POLE | S 60° W | 87.02'  | NAIL |
| (8) DE POLE  | N 65° W | 162.48' | NAIL |

Robert A. Campbell, Jr., RLS #13028 - November 1982  
Washtenaw County Records - L.C.R.C. Liber 6 Page 262  
Found 4" Steel Monument. Raised to surface with 3/4" x 9"  
Iron Pipe in Monument Box over 4" Steel Monument

- |               |         |         |                 |
|---------------|---------|---------|-----------------|
| (8) P. POLE   | N 75° W | 162.37' | FD NAIL S. SIDE |
| (7) P. POLE   | n 82° E | 148.96' | FD NAIL N. SIDE |
| (9) 29" APPLE | N 55° W | 359.3'  |                 |
| (10) 36" PEAR | N 04° E | 400.3'  |                 |