

APPROVED
 DATE 9-23-96
 CO. REP. KA

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 WASHTEENAW COUNTY, MI
 FEB 18 9 10 AM '97
 PEGGY M. HAINES
 COUNTY CLERK/REGISTER

For corners in <u>Washtenaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>6E</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 00001 Page 0607 pm

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Todd D. Shelly, in a field survey on 3-22, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 See back of sheet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 3/4" IP with "W.C.R.C." cap in monument box 3-15-96
 See back of sheet.

SURVEY &
 REMONUMENTATION

MAY 05 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Found 3/4" IP with "W.C.R.C." cap in monument box. Set aluminum remonumentation cap with PK nail in center over found iron pipe.

- 5) 14" Hickory S27°W 60.10' to nail & RT
- 6) Twin 10" & 14" Hickory S37°W 45.54' to nail & RT
- 16) 12" Hickory N28°W 67.39' to nail & RT
- 20) Telephone pole N30°E 72.02' to nail & RT

COPY

I believe that this point should be accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Todd D. Shelly Date Nov 25
 Surveyor's Michigan License No. 41111

TODD D. SHELLY
 PROFESSIONAL SURVEYOR
 No. 41111
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Date	Surveyor	Notes	Grid Book
11-18-1887	C.S. Woodard	Iron bar, tile and stone.	
1) 10" Maple	N85°E	372.2'	
2) 12" Apple	N26°E	148.5'	Liber 000001 Pa- 0602
4-8-1932	W.J. Armstrong	Found state monument.	Grid Book
3) 8" Elm	N13°E	78.93'	
4) 14" Locust	N66°E	72.68'	
5) 5" Hickory	S29°W	59.5'	
6) 5" Hickory	S33°W	44.6'	
7) 12" Locust	N26°W	50.0'	
8) 3 R.O.W. pipes			
5-27-1958	C. Wilson	Found steel encased mon. 1.3 below surface of road.	A-H Book 660-6 Raised with 1/2" x 12" I.P.
8-27-1971	N. Fahrner No. 17620	Monument.	LCRC L.1, P.237
3) Stump	N13°E	78.9'	
4) Stump	N66°E	72.7'	
5) 14" Hickory	S29°W	60.1'	
6) 14" Hickory	S33°W	44.6'	
9) 15" Locust	S85°W	28.4'	
1-6-1976	P. Schwimmer	Found re-rod in mon. box in centerline of road.	A-H Book 782-52
10) 16" Hickory	S30°E	62.6'	
11) 48" Oak	S65°E	92.7'	
12) 12" Ash	N34°W	56.6'	
13) 16" Hickory	S65°W	82.0'	
8-2-1978	R.J	Found 1" iron pipe.	Survey Job #78-6-399
9) Locust tree	S80°W	28.41' nail	
14) Pipeline marker	S40°E	46.7'	
15) P.P.	S30°E	61.59' nail	
16) 12" Hickory	N30°W	67.38' nail	
8-31-1978	Washtenaw Engineering	Monument.	Survey File No. R-4224
3) Stump	N13°E	78.9'	
4) Stump	N66°E	72.7'	
5) 14" Hickory	S29°W	60.1'	
6) 14" Hickory	S33°W	44.6'	
9) 15" Locust	S85°W	28.4'	
6-18-1979	Washtenaw Eng.	Found 1" I.P.	Survey File No. R-4408
9) Locust tree	S80°W	28.41' nail	
14) Pipeline marker	S40°E	46.7'	
15) P.P.	S30°E	61.59' nail	
16) 12" Hickory	N30°W	67.38' nail	
6-29-1979	N. Fahrner No. 17620	Monument.	LCRC L.5, P.230
5) 10" Hickory	S29°W	60.1'	
6) 10" Hickory	S33°W	44.6'	
8) R/W iron WEST	32.55'		
15) P.P.	S35°E	61.67' nail	
10-15-1979	R. Campbell No. 13028	Found 4" steel encased concrete monument. Raised to surface with 3/4" I.P. and plastic plug, over monument. Set monument box at surface of new asphalt roadway.	LCRC L.5, P.250
5) 14" Hickory	S31°W	60.12' nail SE side	
6) 11" Tw. Hickory	S44°W	45.55' nail SE side	
15) P.P.	S25°E	61.67' nail W. side	
17) 27" Apple	N84°W	90.8'	
18) 15" Tw. Hickory	S23°W	67.2'	
12-5-1979	John Snyder	Found 3/4" I.P.	A-H Drw. 535-112
5) 10" Hickory	S29°W	59.5'	
6) 10" Hickory	S33°W	44.6'	
8) R.O.W. pipe	WEST	33.0'	
3-28-1980	A-H	Found 3/4" I.P. in box.	A-H Book 810-49
5) 8" Tw. Hickory	S27½°W	60.15' to PK	
6) 7"-8" Tw. Hickory	S37½°W	45.55' to PK	
16) 14"-14" Forked Hickory	N28°W	67.3' to PK	
17) 39" Apple	N88°W	90.6'	
19) PP	S32°E	81.65' to PK	
4-30-1980	Morris Levine No. 11076	Found monument with 1/2" I.P. with WCRC cap.	Survey L.1757, P.244
6) 12" Hickory	S36°W	44.66' N&W	
9) 24" Tree WEST	28.43' N&W		
15) P.P.	S26°E	61.62' N&W	
16) 10" Hickory	N23°W	67.45' N&W	
3-18-1994	R. Macomber	Found 3/4" I.P. in box.	A-H Drw. 535-168
5) 12" Hickory	S27½°W	60.15' to PK	
6) 8" & 12" Tw. Hickory	S37½°W	45.45' to PK	
16) 10" Tw. Hickory	N28°W	67.3' to PK	
19) P.P.	S32°E	81.65' to PK	
3-15-1996	Atwell-Hicks, Inc.	Found 3/4" I.P. with "W.C.R.C." cap in monument box. with PK nail in center over found iron pipe.	Remonumentation Set aluminum remonumentation cap
5) 14" Hickory	S27°W	60.10' to nail & RT	
6) Tw. 10" & 14" Hickory	S37°W	45.53' to nail & RT	
16) 12" Hickory	N28°W	67.39' to nail & RT	
20) Telephone pole	N30°E	72.02' to nail & RT	