

APPROVED

DATE 9-23-96

CO. REP. KA

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
WASHTENAW COUNTY, MI  
FEB 18 9 24 AM '97  
PEGGY N. HAINES  
COUNTY CLERK/REGISTER

For corners in

<u>Washtenaw</u> (County)	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>3S</u> R <u>6E</u>	<u>J-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber 00001 Page 0681 *BM*  
Register of Deeds Stamp & File Number

I, Todd D. Shelly, in a field survey on 3-22, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5, above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented; re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
See back of sheet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1" IP, rocks and tile 3-12-96  
See back of sheet.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Found 1" IP, rocks and tile. Set 3/4" IP with aluminum remonumentation cap with PK nail in center over found iron pipe.

- 5) 28" Triple Oak N'ly 92.80' to nail & RT
- 6) 38" Cherry S'ly 103.50' to nail & RT
- 7) N.W. corner garage N30°E 52.10'
- 8) 11" Poplar S80°W 33.61' to nail & RT

COPY

I believe that this point should be accepted as a careful and faithful reproduction of the position of the original corner.

Signed by Todd D. Shelly  
Surveyor's Michigan License No. 41111

Date Nov 23 1996  
TODD D. SHELLY  
PROFESSIONAL SURVEYOR  
No. \_\_\_\_\_

## J-9 Witness Summary

11-18-1887 C.S. Woodard

Woodard's notes

Stake, tile, stone.

1) 6" Spruce	S71°W	34.3'
2) 18" Hickory	S30½°E	95.7'
3) 12" Apple	S33½°W	65.0'

June 1941 E. Young

Grid Book

No description of monument.

1) 20" Spruce	S71°W	34.3'
4) Tw. Cherry	N'ly	18.5'
5) 7" Oak cluster	N'ly	92.8'
6) 14" Cherry	S'ly	103.5'

7-10-1973 J. Oliver No. 19840

LCRC L.3, P.229

1) 28" Spruce	S71°W	34.4'
4) 31" Cherry	N'ly	18.5'
5) 22" Oak cluster	N'ly	92.8'
6) 24" Cherry	S'ly	103.5'

11-9-1977 Paul Schwimmer

A-H book 804-23

Found 1" iron pipe 0.4' east of N-S fence.

1) 24" Spruce	S71°W	34.4'
4) 36" Tw. Cherry	N'ly	18.5'
7) N.W. cor. garage	N30°E	52.1'

3-12-1996 Atwell-Hicks, Inc.

Remonumentation

Found 1" I.P., rocks and tile.

Set 3/4" I.P. with Aluminum

Remonumentation cap with PK nail in center over found iron pipe.

5) 28" Triple oak	N'ly	92.80' to nail & RT
6) 38" Cherry	S'ly	103.50' to nail & RT
7) N.W. corner garage	N30°E	52.10'
8) 11" Poplar	S80°W	33.61' to nail & RT