

Copy -

"A" continued...

11-1887	C.S. Woodard		Woodard's notes
Stake, brick & stone.			
3)	10" Maple	N38½°W	40.9
4)	10" Maple	N72°W	93.1
1929	MDOT		Survey Drw. 048-3D
3)	24" Maple	N38°05'W	41.3
5)	16" W. Oak	N16°35'E	88.2
6)	8" B. Oak	N34°45'E	80.0
7)	6" Maple	S74°E	79.5
8)	4" Cherry	S65°10'E	59.4
9)	30" B. Locust	S80°25'W	192.2
8-31-1934	W.J. Armstrong		Grid
Found an iron pipe and stones. Did not reset.			
3)	30" Maple	N35°W	41.0
5)	28" W. Oak	N14°W	88.0
6)	12" B. Oak	N37½°E	80.1
10)	6" Cherry	S58°W	53.5
11-9-76	Control Survey Assoc.		Survey
5)	28" W. Oak	N14°W	88.0
6)	12" B. Oak	N37½°E	80.1
12-29-76	Norman Fahrner		LCRC L.4, P.278
Found I.P.			
3)	30" stump	N35°W	41.0
5)	28" W. Oak	N14°W	88.0
6)	12" B. Oak	N37°E	80.1
11)	Tele. pole	S60°W	61.0
12)	P.P.	N60°W	81.0
13)	Tw. stump	S05°E	32.4
5-12-77	Arthur A. Ivey		LCRC L.4, P.207
Found 1 1/4" I.P. buried in gravel about 0.3', about 3' north of CL of Bemis and about 127' east of CL of Carpenter Road pavement.			
6)	23" R. Oak	N37°E	80.10
12)	Pk. S'ly side P.P.	WNW	81.02
14)	Top center of hydrant	WSW	82.50
15)	10d nail NE side T. pole	ESE	84.65
10-3-77	Robert A. Campbell		LCRC L.4, P.390
Found 1" I.P.			
11)	Tele. pole	S68°W	60.88
12)	P.P.	N64°W	80.96
14)	Hydrant	S74°W	82.45
15)	Tele. pole	S62°E	84.79
11-16-78	Robert A. Campbell		
Set 3/4" X 18" I.P. over conc. mon.			
6)	24" B. Oak	N44°E	79.72 nail NW side
11)	T.P.	S65°W	60.81 nail NW side
12)	P.P.	N62°W	80.88 nail SW side
14)	Top nut hydrant	S74°W	82.39
15)	T.P.	S64°E	84.89 nail NE side
1-24-79	Roskelly, Jekabson & Assoc.		Survey
Found capped I.P.			
6)	20" B. Oak	N35°E	79.71 nail
12)	P.P.	N60°W	80.82 nail
14)	Hydrant	S70°W	82.40
15)	M.B.T. pole	S70°E	84.86 nail
6-25-90	Washtenaw Engineering		Survey
3)	30" stump	N35°W	41.0
12)	P.P.	N60°W	81.00 nail
13)	Tw. stump	S5°E	32.4
14)	Top nut hydrant	S70°W	82.10
"C" continued...			
11-24-1995	Atwell-Hicks, Inc.		Remonumentation
Set remon. cap on found 3/4" I.P. in mon. box.			
6)	24" B. Oak	N37½°E	79.60 nail & R.T.
12)	P.P.	N60°W	80.90 nail & R.T.
14)	Hydrant	S70°W	82.02 top nut
15)	16" Oak	N13°W	58.52 nail & R.T.
16)	14" Tw. Locust	S50°E	46.46 nail & R.T.
17)	K-1 YORK TWP	WEST	164.27

APPROVED

DATE 4/24/95CO. REP. K