

**SURVEY & REMONUMENTATION**

- Copy -

MAY 09 1996  
COMMISSION

**REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>6E</u>	<u>M-13</u>
	T <u>35</u> R <u>6E</u>	<u>M-1</u>
	T <u>25</u> R <u>7E</u>	<u>A-13</u>
	T <u>35</u> R <u>7E</u>	<u>A-13</u>
2. Property Controlling in Section	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	

RECORDED  
 WASHTENAW COUNTY, MI  
 MAR 29 1 39 PM '96  
 COUNTY DEED REGISTER  
 - COPY -

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, R.T. Tietsema in a field survey on 12/17 1995, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate**

**A. Description of original monument and accessories and/or subsequent restoration:**

1817	GLO		Fld. Notes	Set Original Corners	1) 24" W. Oak 2) 24" W. Oak	N10W S10E	12 links (7.92') 39 links (25.74')
				Set post corner of Ts2&3, R 6&7E			
Unknown	H.H. Atwell			Iron Pipe	3) 14" Elm 4) 18" Hickory 5) 8" Forked Cherry 6) Conc. Post	SW W of S SE North	41.9' 65.5' 50.8' 24.7' to south side
12/14/1988	R.A. Campbell, JR	I3028	L7P203	Fnd. 3/8" bar in pvmt. Reset with 3/4"x18" Iron Pipe with cap in mon. box	7) U. Pole 8) Manhole 9) Hydrant 10) Top of SW cor. conc. pad traffic control box	S40E SLY S67W N42E	65.42' to PK nail 16.8' to center 72.78' to top nut 75.08'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" capped (non-readable) Iron Pipe in Mon. Box.  
 Also found remaining accessories:

7) U. Pole	S40E	65.42' to PK nail
8) Manhole	SLY	16.8' to center
9) Hydrant	S67W	72.78' to top nut
10) Top of SW cor. conc. pad traffic control box	N42E	75.08'

**APPROVED**  
 DATE 12/11/95  
 CO. REP. [Signature]

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Remonumentation Cap on existing 1" capped (non-readable) Iron Pipe in Mon. Box.

It is my opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date 18 DEC 95  
 Surveyor's Michigan License No. 20712