

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
WASHTENAW
 (County)


Located in: YPSILANTI
 TOWNSHIP

Corner Code #

- 1. Public Land Survey T 3 S R 7 E
- 2. Property controlling in Section S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plot _____
- 5. Private Claims _____

F-13

Copy



5094788
 Page: 1 of 1
 02/07/2000 02:55P
 L-3 P-82
 Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 3, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, reestablished, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

- A. Description of original monument and accessories and/or subsequent restoration:
- ORIG. GOVERNMENT NOTES 1819
 WITNESSED BY JOSEPH WAMPLER - SET POST
 - 1) ASH 12" WEST 16 LINKS
 - 2) ASH 12" S75°E 9 LINKS
 - NO G.L.O. WITNESSES REMAIN
 - W.C.R.C. FIELD NOTES TRANSCRIBED FROM W.J. ARMSTRONG NOTES 9/20/34
 - 1 1/2" IRON PIPE WITH BRICKS AND STONES
 - 3) 6" HICKORY N01°W 46.0'
 - 4) 12" HICKORY NORTH 90.4'
 - 5) 24" HICKORY S11°E 20.4'
 - 6) 40" ELM S77°W 73.0'
 - 7&8) 2 R/W PIPES
 - P.A. 132 L.1397 P.515 BY HOWARD W. TAFT #12032 5/22/72
 - FOUND 1 1/2" IRON PIPE
 - 5) 28" HICKORY S11°E 20.4'
 - 6) STUMP OF ELM S80°W 73.0'
 - 9) P. POLE N70°W 153.8'
 - 10) P. POLE S70°W 192.0'
 - P.A. 74 L.2, P.497 & P.A. 132 L.1425, P.52 BY ROBERT J. JAGOW #6998 12/27/72
 - FOUND 1 1/2" IRON PIPE. FOUND ONE WITNESS TREE AND STUMP OF 40" ELM
 - 5) 30" HICKORY S11°E 20.4'
 - 6) FOUND STUMP OF 40" ELM NO TIES
 - 9) P. POLE N62°W 154.2'
 - 10) P. POLE S79°W 192.4'
 - 11) P. POLE N80°E 270.7'
 - 12) FENCE LINE SOUTH 32.5'
 - P.A. 74 L.8, P.269 BY THADDEUS A. WOZNAK #15066 5/6/98
 - FOUND 1 1/2" IRON PIPE
 - 7) FOUND CAPPED IRON PIPE NORTH 33.00'
 - 9) P.K. #14864 SOUTH SIDE OF U. POLE N70°W 153.86'
 - 13) P.K. NAIL IN EAST SIDE OF 3" CHERRY S20°E 26.99'
 - 14) P.K. NAIL IN SOUTH SIDE OF TRIPLE 8" ELM N85°W 128.80'

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:
 F-13 SOUTH 1/4 CORNER OF SECTION 33, YPSILANTI TOWNSHIP
 FOUND "MUSHROOMED" 1" IRON PIPE DRIVEN INTO BENT 1 1/2" IRON PIPE AT CENTER OF BRICK AND STONE 12" BELOW GRAVEL SURFACE. STRAIGHTEN 1 1/2" IRON PIPE AND DROVE 1" IRON PIPE OVER IT THEN PLACED REMON CAP ON TOP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1" IRON PIPE WITH ALUMINUM REMONUMENTATION CAP STAMPED #41914
 7) FOUND CAPPED IRON PIPE #14864 NORTH 32.97'
 9) SET REMON TAG OVER FOUND P.K. & DISC #14864 SOUTH SIDE OF U. POLE N70°W 153.82'
 12) FENCE LINE SOUTH 32.5'
 13) SET REMON TAG OVER FOUND P.K. NAIL & RIBBON IN EAST SIDE OF 3" TWIN HAWTHORN S20°E 26.95'
 15) SET REMON TAG OVER FOUND 20d NAIL WEST SIDE OF TWIN 3" HAWTHORN S20°W 25.80'
 16) SET REMON TAG OVER FOUND NAIL & DISC STAMPED "OHM KSW #21584 N80°E 270.32'

I CONCLUDE AFTER CAREFUL STUDY OF THE RECORD DOCUMENTATION AND FIELD OBSERVATIONS, THAT THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. THIS POINT WAS RATIFIED BY THE WASHTENAW COUNTY PEER COMMITTEE ON DECEMBER 20, 1999.

Signed by Christopher S. Lamus
 Surveyor's Michigan License No. 41914



Date 12/21/99

APPROVED
 DATE 12/20
 CO. REP. K