

RECEIVED

SURVEY & MAPPING

MAR 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW
(County)

Located In: YPSILANTI TOWNSHIP

Corner Code #

- 1. Public Land Survey T 3 S R 7 E G-13
- 2. Property controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

Copy



5094793
Page: 1 of 1
02/07/2000 02:55P
L-3 P-87

Peggy M. Haines - Washtenaw Co. CORREM

Register of Deeds Stamp & File Number

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 3, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, reestablished, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

ORIG. GOVERNMENT NOTES 1819
 WITNESSED BY JOSEPH WAMPLER - SET POST
 1) BEECH . 12" S38°W 40 LINKS
 2) BEECH 24" N28°W 9 LINKS
 NO G.L.O. WITNESSES REMAIN
 W.C.R.C. FIELD NOTES TRANSCRIBED FROM W.J. ARMSTRONG NOTES 9/18/34
 1 1/2" IRON PIPE WITH BRICKS AND STONES
 3) N.E. CORNER OF BARN S52°E 67.5'
 4) N.W. CORNER OF BARN S41°W 64.7'
 5) 30" MAPLE S82°W 134.0'
 6&7) 2 R/W PIPES
 8) CORNER TO AUGUSTA TWP., CORNERS COMMON TO SECTION 3 & 4 WEST 199.40'

P.A. 74 THADDEUS A. WOZNIAK # 15066
 L.B. P.269 -5/6/1998
 FOUND 3/4" BOAT SPIKE 8" BELOW GRAVEL
 9) P.K. NAIL IN NORTH SIDE OF 10" MAPLE S50°E 87.40'
 10) P.K. NAIL #14864 NORTHWEST SIDE OF 10" TREE S40°W 52.44'
 11) P.K. NAIL IN NORTH SIDE T. POLE S80°W 108.40'
 12) P.K. NAIL SOUTH SIDE P. POLE N75°W 108.30' (POSSIBLE TYPO 100.30')

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

FOUND 3/4" BOAT SPIKE 3" BELOW GRAVEL SURFACE INSIDE 1 1/2" IRON PIPE SURROUNDED BY BRICKS AND STONES 9" BELOW GRAVEL SURFACE. BRICKS FOUND AT 12" BELOW GRAVEL SURFACE. SET 3/4" IRON PIPE OVER THE 1 1/2" IRON PIPE AND THE 3/4" BOAT SPIKE THEN SET REMON CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" IRON PIPE WITH ALUMINUM REMONUMENTATION CAP STAMPED #41914
- 8) AUGUSTA TWP., CORNER COMMON TO SECTION 3&4 WEST 199.41'
- 9) SET REMON TAG OVER FOUND MAG NAIL IN NORTH SIDE 10' MAPLE S35°W 52.37'
- 10) SET REMON TAG OVER FOUND MAG NAIL IN WEST SIDE OF 14" MAPLE S35°W 52.37'
- 11) SET REMON TAG OVER FOUND P.K. NAIL IN NORTH SIDE OF T. POLE S76°W 108.43'
- 12) SET REMON TAG OVER FOUND P.K. NAIL IN SOUTH SIDE OF P. POLE N72°W 100.30'
- 13) FOUND P.K. NAIL AT CL-CL OF BEMIS AND WHITTAKER ROADS INTERSECTION WEST 189.32'

I CONCLUDE AFTER CAREFUL STUDY OF THE RECORD DOCUMENTATION AND FIELD OBSERVATIONS, THAT THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. THIS POINT WAS RATIFIED BY THE WASHTENAW COUNTY PEER COMMITTEE ON DECEMBER 20, 1999.

Signed by Christopher S. Lamus
Surveyor's Michigan License No. 41914



12/21/99

APPROVED
DATE 12/20/99
CO. REP. KJ