

REM

NOV 10 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW
(County)

Located In: YPSILANTI TOWNSHIP

Corner Code #

- 1. Public Land Survey T 3 S R 7 E
2. Property controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

H-13



5094796
Page: 1 of 1
02/07/2000 02:55P

Peggy M. Haines - Washtenaw Co. CORREM L-3 P-90

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at row 13, column H.

I, CHRISTOPHER S. LAMUS, in a field survey on NOVEMBER 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, reestablished, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- ORIG. GOVERNMENT NOTES 1819 WITNESSED BY JOSEPH WAMPLER SET POST
1) HICKORY 18" N73°E 9 LINKS
2) ASH 15" S43°W 29 LINKS
NO G.L.O. WITNESSES REMAIN
W.C.R.C. W.J. ARMSTRONG 9-18-34 SET 1 1/2" IRON PIPE WITH BRICK & STONES
3) 30" LOCUST S17°W 29.0'
4) 30" LOCUST S79°W 118.1
5) 24" MAPLE N75°W 113.2'
6) 28" MAPLE N67°W 76.5'
7) R/W IRON NORTH 33.00'
8) R/W IRON SOUTH 33.00'

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

H-13 SOUTH 1/4 CORNER SECTION 34, YPSILANTI TOWNSHIP. FOUND 3/4" (O.D.) 1/2" (I.D.) IRON PIPE 3" BELOW GRAVEL SURFACE DUG 13" BELOW GRAVEL SURFACE TO BRICK SURROUNDING THIS IRON PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" IRON PIPE WITH ALUMINUM REMONUMENTATION CAP STAMPED #41914
13) FOUND P.K. NAIL IN N.E. SIDE OF 3" STEM OF MULTI-STEM ASH S60°W 46.96'
15) SET REMON TAG OVER FOUND P.K. NAIL IN SOUTH SIDE OF P. POLE N30°E 26.33'
16) SET REMON TAG OVER FOUND P.K. NAIL & 30d DISC IN SOUTH SIDE OF P. POLE N40°E 38.97'
17) SET REMON TAG OVER FOUND 60d NAIL WEST SIDE OF WESTERLY MULTI-STEM MAPLE N1°E 60.52'
18) SET REMON TAG OVER FOUND 60d NAIL IN NORTH SIDE OF 20" ASH S84°W 255.10'
19) FOUND P.K. NAIL & WASHER SOUTH SIDE OF P. POLE N86°W 315.61'

I CONCLUDE AFTER CAREFUL STUDY OF THE RECORD DOCUMENTATION AND FIELD OBSERVATIONS, THAT THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. THIS POINT WAS RATIFIED BY THE WASHTENAW COUNTY PEER COMMITTEE ON DECEMBER 20, 1999.

Signed by Christopher S. Lamus
Surveyor's Michigan License No. 41914



APPROVED DATE 12/20/99 CO. REP. [Signature]