

**SURVEY & REMONUMENTATION**

*- Copy -*

MAY 09 1996

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

K-09 Page 1

For corners in Washenaw  
County Wayne

Located in: YPSILANTI Corner Code K-09

- |                                       |         |                           |             |
|---------------------------------------|---------|---------------------------|-------------|
| 1. Public Land Survey                 |         | T <u>3</u> S R <u>7</u> E | <u>K-09</u> |
|                                       |         | T _____ R _____           | _____       |
|                                       |         | T _____ R _____           | _____       |
|                                       |         | T _____ R _____           | _____       |
| 2. Property Controlling In Section    | S _____ | T _____ R _____           | _____       |
|                                       | S _____ | T _____ R _____           | _____       |
| 3. Miscellaneous Property in Sec.     | S _____ | T _____ R _____           | _____       |
|                                       | S _____ | T _____ R _____           | _____       |
| 4. Lot No. _____, Recorded Plat _____ |         |                           |             |
| 5. Private Claims _____               |         |                           |             |

RECORDED  
 WASHENAW COUNTY, MICH.  
 MAR 29 1 45 PM '96  
 PEER & MAINES  
 COUNTY CLERK/REGISTRAR  
 Register of Deeds Stamp and File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael S. Hoben in a field survey on 03/01/1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:

- 11/23/1816 G.L.O. SET POST
- 1 11" W. OAK W. 26 LINKS
  - 2 20" DOGWOOD S. 50 LINKS E. 29 LINKS

(Witnesses Continued on Back ...)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3/4" I.P. near S. edge asph. pave. on Textile Rd. dist. To L-09=2615.19' (M), 2615.5'(WCR-1936), angle 91-49-27 (M) 91-47-30( Armstrong-1941). Dist. to K-10=2630.04'(M), 2630.70'(1937)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

03/01/1995 Hoben 35994 O.H.M. Remon

- Set W.C.R. remon cap over corner.
- 6 P.K. nail in D.E. Pole N 35 W 60.20'
  - 10 Set W.C.R. washer in D.E. pole. S 30 W 86.17'
  - 11 P.K. in light pole S 45 E 44.90'
  - 12 Top bolt in Hyd. S 35 W 69.54'



We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by Michael S. Hoben Date 12-18-95  
 Drafted by Michael S. Hoben  
 Surveyor's Michigan License No. 35994

## A. (Continued) Description of original monument and accessories and/or subsequent restorations:

11/22/1933	J.F. MARZENE		
	1 12" MAPLE S. 65 W. 47.3'		
	2 10" MAPLE S. 20 W. 93.2'		
	3 14" MAPLE S. 40 W. 53.2'		
	4 20" OAK N. 2 W. 60.5'		
03/03/1936	ATWELL	ATWELL- HICKS	NOT GIVEN
	DIST TO M-09 = 2720.5'		
	DIST TO K-09 = 2615.5'		
05/02/1936	W.C.R.		NOT GIVEN
	DIST. TO K-10 2615.5'		
06/06/1937	J. KAART		
	DIST TO K-10 = 2630.70'		
04/06/1942	ATWELL	ATWELL- HICKS	NOT GIVEN
	DIST TO M-09 = 2610.02'		
02/02/1960		W.C.R.C.	NOT GIVEN
	5 NAIL IN T. POLE S.WLY 59.93'		
	6 NAIL IN THE WLY 60.43'		
	7 NAIL IN T. POLE SELY 63.20'		
	8 4" CONC. MARKER NLY 50.00"		
02/01/1968		ATWELL- HICKS	NONE GIVEN
	DIST TO L-09 = 2614.95'		
	WITNESSES ARE THE SAME AS ABOVE		
05/30/1972	RENTSCHLER 15411	L 2P3	3/4" IRON PIPE
	WITNESSES ARE THE SAME AS ABOVE		
05/26/1976	R. BURRIS, SR. 19563	L.5 P.	FD. 1/2" IRON NEAR S. EDGE OF PAVEMENT ON TEXTILE RD.
	5 P.K. NAIL IN P.POLE S. 49 W. 60.00'		
	6 P.K. NAIL IN P.POLE N. 35 W. 60.20'		
	9 CONC. R.O.W. POST N. 49.80'		
	10 P.K. NAIL IN P. POLE S. 30 W. 86.10'		
01/27/1980		W.C.R.C.	NONE GIVEN
	DIST. BETWEEN K-09 & L-09 = 2615.5'		

APPROVED

DATE 12/4/95

CO. REP. KA