

Copy -

MAY 09 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

K-10 Page 1

For corners in

Wayne *Washtenaw*

Located in:

Corner Code

County

YPSILANTI

1. Public Land Survey		T <u>3</u> S R <u>7</u> E	K-10
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Register of Deeds Stamp and File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Michael S. Hoben in a field survey on 03/01/1995
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:

11/23/1816 G.L.O. SET POST
5" ASH S. 63 LINKS E. 10 LINKS
5" W. OAK S. 60 LINKS W. 13 LINKS


(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. Boat Spike over 1 1/2" split I.P.dist.. to K-11=2624.12' (M), 2624.35' (A.H.-1986), dist to k-09=2630.04'(M),2630.70'(1937)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

03/01/1995 Hoben 35994 O.H.M. Remon
Set W.C.R. remon cap over corner.
5 Set W.C.R. tag in 24" tree N 89 W 42.15'
8 Set W.C.R. tag in D.E. pole N 89 E 52.15'
9 Top of Hyd. N 10 W 115.14'
10 Set W.C.R. tag in 6" Maple N 30 E 77.25'
11 Set W.C.R. tag in 12" tree S 85 E 33.69'



RECORDED
WASHINGTON COUNTY, MI
MAR 29 1 45 PM '96
PERCIVAL JAMES
COUNTY CLERK REGISTER

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by Michael S. Hoben Date 12-18-95

Drafted by Michael S. Hoben
Surveyor's Michigan License No. 35994

Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

- Copy -

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1935	GRAF	W.C.R.C.	NOT DESCRIBED
1	10" OAK S76W 44.3'		
2	17" B. ASH S. 58 W. 55.10'		
3	24" ELM S. 21 W. 90.8'		
4	IRON BAR DUE E. 33.0'		
5	14" POPLAR N. 80 W. 42.23'		
06/06/1937	J KAART	W.C.R.C.	NOT DESCRIBED
	DIST. TO K-09=2630.70'		
02/01/1968		ATWELL- HICKS	NONE GIVEN
	DIST. TO K-11=2624.33'		
	WITNESSES ARE SAME AS ABOVE		
12/10/1986	SNYDER	13352 ATWELL- HICKS	BOAT SPIKE IN CENTER OF STREET
5	24' TREE W. 42.0'		
6	CL. OF HYD. N. 10 W. 115.14'		
7	FENCE CORNER N. 85 E. 30.90'		
8	UTILITY POLE E. 52.20'		

APPROVED

DATE 10/16/95CO. REP. RA