

MAY 09 1996

- Copy -

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

K-11 Page 1

For corners in

Washtenaw
Wayne

Located In:

Corner Code

YPSILANTI

K-11

- 1. Public Land Survey T 3 S R 7 E _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

REGISTERED
 WASHTENAW COUNTY, MI
 MAR 29 1 45 PM '96
 PEGGY A. JAINES
 COUNTY CLERK/REGISTER
 - COPY -
 Register of Deeds Stamp and File Number

I, Michael S. Hoben in a field survey on 03/01/1995
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restorations:

- 11/23/1816 G.L.O. SET POST
- 1 18" ASH S. 14 LINKS W. 11 LINKS
- 2 20" LYNN N. 44 LINKS W. 23 LINKS

(Witnesses Continued on Back ...)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1". I.P. in mon box in asph pave. Dist to L-11 = 2619.55'(M), 2619.70(1992), dist. to K-10 = 2624.12(M), 2624.33(1988), angle=88-54-44.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

03/01/1995 Hoben 35994 OHM REMON

- SET W.C.R. REMON. CAP OVER CORNER
- 10 SET TAG IN DE POLE S 89 W 65.60'
- 20 SW LEG OF TOWER NE 40.20'
- 21 TOP OF HYD. S 30 E 44.90'
- 23 SET TAG IN POST E 32.00'
- 24 FD. 1" IRON ROD W. 33.00'



REGISTERED
 WASHTENAW COUNTY, MI
 MAR 29 1 45 PM '96
 PEGGY A. JAINES
 COUNTY CLERK/REGISTER
 - COPY -

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by Michael S. Hoben Date 12-18-95

Drafted by Michael S. Hoben

Surveyor's Michigan License No. 35994

Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1938					NONE GIVEN
	3	6" ORANGE N. 51.5 E. 42.4'			
	4	WLY COR. H. TOWER N. 57.5 E. 40.0'			
	5	12" PIN OAK S. 22.5 E. 66.5'			
	6	24" ELM S. 11.5 W. 108.9'			
	7	10" B. HICKORY S. 78.5 W. 24.8'			
	8	SLY COR. H. TOWER N. 77 E. 48.9'			
02/01/1968		ATWELL- HICKS			NONE GIVEN
	9	SAME AS ABOVE			
10/09/1973	H. NOWAK	13300		L. 3 P	FOUND 1 1/2" DIA. IRON PIPE
	10	PK IN DE. POLE S. 89 W. 65.66'			
	11	PK IN FENCE POST N. 62 E. 34.64'			
	12	PK IN DE. POLE S. 72 E. 33.37'			
09/07/1976		ROSKELLY, JEKABSON			FD. 1" IRON PIPE
	10	NAIL IN DE. POLE W. 65.63'			
	13	IRON PIPE E. 33.00'			
	14	NAIL IN 8" HICKORY S. 30 W. 52.17'			
	15	PIPELINE MARKER N. 70 W. 28.83'			
09/27/1976		ROSKELLY, JEKABSON			FD. 1" IRON PIPE
	14	SAME AS ABOVE			
	16	DIST. TO L-11=2619.84'			
12/02/1983	K. NIXON	13028	W.C.R.C.	L. 7 P	RESET WITH 3/4" X 18" I.P. IN MON. BOX OVER 1" I.P.
	17	S. END OF DRIVE CULVERT S. 53D E. 34.68' SET PK			
	18	E. EDGE OF PAVEMENT E. 13.9'			
	19	W. EDGE OF PAVEMENT W. 9.7'			
12/15/1986	SNYDER	13352	ATWELL- HICKS		IRON ROD IN MON. BOX
	10	NAIL IN UTILITY POLE W. 65.60'			
	20	TOP BOLT IN MOST WLY LEG OF DE. TOWER N. 70 E. 40.38'			
	21	CL HYD. S. 60 E. 44.80'			
	22	CL. GATE VALVE & WELL S. 70 W. 47.70'			
02/14/1992	BLANCHARD	27446	E.P.K.	PARCEL SURVEY	MON. NOT DESCRIBED
		DIST TO L-11=2619.70'			

APPROVED

DATE

12/4/95

CO. REP.

19