

SURVEY & REMONUMENTATION

MAY 09 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

- Copy -

L-09 Page 1

COMMISSION

For corners in Washtenaw
Wayne

County	Located in:	Corner Code
	YPSILANTI	
1. Public Land Survey	T 3 S R 7 E	L-09
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp and File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Michael S. Hoben in a field survey on 03/01/1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:

- 11/24/1816 G.L.O. SET POST
- 1 5" B. OAK S. 30 LINKS E. 34 LINKS
- 2 14" DOGWOOD S. 84 LINKS W. 31 LINKS


(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. R.R. spike in old asph. rd. under new asph. rd. Dist to K-09 = 2614.95' (R), 2615.19'(M). Dist to M-09 = 2610.02' (R), 2610.12'(M)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 03/01/1995 Hoben 35994 OHM REMON
- SET W.C.R.C. REMON CAP OVER CORNER
- 10 SET TAG IN DE POLE S23E 76.02'
- 11 FD. P.K. W/TAG IN DE POLE N3E 48.96'
- 12 FD. P.K. W/TAG IN GUY POLE N42W 50.78'
- 16 SET W.C.R. TAG IN GUY POLE S65E 80.65'



RECORDED
WASHTENAW COUNTY, MI
MAR 29 1 46 PM '96
REGISTER
COUNTY OF WASHTENAW
- COPY -

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by *Michael S. Hoben* Date 12-18-95
Drafted by Michael S. Hoben
Surveyor's Michigan License No. 35994

Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

APPROVED
DATE _____
CO. REP. _____

- Copy -
L-09 Page 2

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

11/22/1933 ARMSTRONG,
LOWEFD. AN I.R. SET BY J.F.
MARZONE IN 1928. RESET W/
AN I.P., STONES AND BRICKS.

- 3 14" OAK S. 65 E. 81.3'
- 4 8" CHERRY S. 7 E. 83.2'
- 5 6" ORANGE N. 3 E. 28.7'
- 6 24" W. OAK S. 82.5 E. 133.8'
- 7 12" APPLES. 41 E. 126.5'
- 8 6" APPLE S. 83 W. 114.5'

02/01/1968

ATWELL-
HICKS

SPIKE?

- 7 12" APPLE S. 41 E. 126.5'
- 9 NE. COR. FORD FENCE S. 45 W. 64.8'
- 10 SPIKE W. SIDE P. POLE S. 30 E. 76.45'
- 11 SPIKE E. SIDE P. POLE N. 48.95'
- 12 SPIKE SW. SIDE GUY POLE N. 30 W. 51.00'
- 13 PT. 1' S. OF CL. BITUMINOUS

06/12/1972 RENTSCHLER 15411 MIDWESTERN

FD. RAILROAD SPIKE

- 10 P. POLE S. 30 E. 76.5'
- 11 P. POLE N'LY 49.0'
- 14 GUY POLE S. 45 W. 60.0'
- 15 CONC. MON. N'LY 50.0'

01/27/1980

W.C.R.C.

- 16 DIST BETWEEN L-09 & M-09 = 2608.0'
- 17 DIST. BETWEEN L-09 & K-09 = 2615.5'

APPROVED

DATE 10/16/95

CO. REP. RA