

SURVEY & REMONUMENTATION

MAR 18 1998

RECORDED
WASHTENAW COUNTY, MI

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 22 8 30 AM '98

For corners in

<u>WASHTENAW</u> (County)	Located In: MANCHESTER TOWNSHIP	Corner Code #
1. Public Land Survey	T 4S R 3E	I-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PEGGY M. HAINES
COUNTY CLERK/REGISTER

- COPY -

- COPY -

Liber 00002 Page 0005 RM
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL V. SCHWIMMER, in a field survey on AUG 19, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

TIME RECORDED 8:30 AM
DATE JAN 22 19 98
PEGGY M. HAINES
WASHTENAW COUNTY CLERK/REGISTER

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.D. (1834) SET 1/4 POST
Y. OAK 14' S 33°E 57 LINKS (1)
W. OAK 24' N 64°W 30 LINKS (2)

ON OCTOBER 2RD, 1934, W.J. ARMSTRONG FOUND THIS ORIGINAL POST AND REPLACED IT WITH A 1 1/2" X 36" IRON PIPE. HIS NOTES DESCRIBE "FOUND THE BLACK STREAK OF AN OLD WOOD STAKE, RESET WITH 1 1/2" X 36" IRON PIPE, STONES AND BRICKS"

N 03°W 35.0' 30° Y. OAK (3) (MEAS 34.52')
S 54°E 88.5' 10" APPLE (4) (GONE)
S 09°E 50.5' 10" APPLE (5) (GONE)
S 64°W 66.5' 20" HICKORY (6) (MEAS 66.33')
N 51°W 54.2' 15" HICKORY (7) (MEAS 54.14')
N 23°W 85.7' S.E. CORNER OF BARN (8) (MEAS 85.9')

2 RIGHT OF WAY PIPES (9)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

WASHTENAW ENGINEERING RECORDED AN ACT 74 (LIBER 4, PAGE 370) FOR I-10 ON DEC. 1ST, 1977. THEY FOUND 4 OF THE ORIGINAL ARMSTRONG WITNESSES AND THE 1 1/2" IRON PIPE.

N 03°W 34.69' 30° OAK W/NAIL (3) N 23°W 85.9' S.E. CORNER OF BARN (8)
S 64°W 66.23' 24" HICKORY W/NAIL (6) S 15°W 24.60' 15" HICKORY W/NAIL (10) (MEAS 24.55')
N 51°W 54.10' 15" HICKORY W/NAIL (7) S 10°E 23.47' 8" HICKORY W/NAIL (11) (MEAS 23.50')

MR. KENNETH SUYDAN, R.L.S., OF WALTER FRAZIER & ASSOC. RECORDED AN ACT 74 (LIBER 5, PAGE 32) ON MARCH 10TH, 1978 FOR A 1/2" IRON PIPE.
N 03°W 33.33' 32" R. OAK W/NAIL & SHINER (3) S 23°E 23.51' 12" HICKORY W/NAIL & SHINER (11)
N 45°W 54.25' 18" HICKORY W/NAIL & SHINER (7) S 10°E 26.43' 12" HICKORY W/NAIL & SHINER (12)
S 65°W 66.13' 24" HICKORY W/NAIL & SHINER (6)


ON 10-30-1978, WASH. ENGINEERING RE-USED THE CORNER ON AN ACT 132 SURVEY AND RECORDED THE SAME WITNESSES AS ABOVE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 3/4" X 12" IRON OVER 1 1/2" IRON SURROUNDED WITH ROCKS AND PIECES OF BRICK. SET ALUM. MONUMENTATION CAP ON FOUND 3/4" IRON.

N 03°W 34.52' SET P.K. NAIL & REMON TAG IN E. SIDE 38" OAK (3)
N 51°W 54.14' SET P.K. NAIL & REMON TAG IN S.W. SIDE 24" HICKORY (7)
S 15°W 24.55' SET P.K. NAIL & REMON TAG IN S.E. SIDE 20" HICKORY (10)
S 50°E 50.91' SET P.K. NAIL & REMON TAG IN N.E. SIDE 15" WALNUT
S 64°W 66.33' SET P.K. NAIL & REMON TAG IN N. SIDE 24" HICKORY (6)
S 23°E 23.50' SET P.K. NAIL & REMON TAG IN W. SIDE 12" HICKORY (11)
S 10°W 26.45' SET P.K. NAIL & REMON TAG IN W. SIDE 12" HICKORY (12)
N 23°W 85.90' SET P.K. NAIL & REMON TAG S.W. CORNER OF BARN (8)

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Paul V. Schwimmer
Surveyor's Michigan License No. 24618

Date Nov 12 1997

APPROVED
DATE 11/10/97
CO. REP. Ks