

SURVEY & REMONUMENTATION

MAR 18 1998

RECORDED
WASHTENAW COUNTY, MI

JAN 22 8 30 AM '98

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

PEGGY M. HAINES
COUNTY CLERK/REGISTER

- COPY -

WASHTENAW (County)	Located In: MANCHESTER TOWNSHIP	Corner Code # I-10
1. Public Land Survey	T 4S R 3E	I-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Liber 00002 Page 0006 RM

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL V. SCHWIMMER, in a field survey on AUG 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.D. (1834) SET 1/4 POST
S 32°E W. OAK 24' .51 CHAINS (1)
N 43°W HICKORY 24' .31 CHAINS (2)

TIME RECORDED 8:30 am
DATE Jan 22 19 98
PEGGY M. HAINES
WASHTENAW COUNTY CLERK/REGISTER

W.J. ARMSTRONG, IN HIS 1930'S REMONUMENT EFFORT DID NOT RESET I-10. THE GRID BOOK STORED BY THE WASH. CO. ROAD COMMISSION ONLY LISTS THE ORIGINAL GOVERNMENT WITNESSES FOR I-10

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 WAS RE-ESTABLISHED BY WASHTENAW ENGINEERING CO. IN 1977 BY SETTING AN IRON PIPE ON A STRAIGHT LINE BETWEEN AND EQUAL DISTANT FROM I-9 AND I-11 (3). HIS WITNESSES ARE AS FOLLOWS:
S 85°E 2.73' 4" TW. APPLE TO NAIL (4) (GONE)
N 45°W 15.18' 4" MULT. ASH TO NAIL (5) (GONE)
S 25°E 15.31' 5" MULT. TH. APPLE TO NAIL (5) (GONE)

IN OUR REMONUMENTATION EFFORT, WE FOUND A 3/4" IRON PIPE WITH A WASH. ENG. PLASTIC CAP. THIS IRON IS ON LINE AND EQUAL DISTANT FROM I-9 AND I-11. DUE TO THE AMOUNT OF ROAD CONSTRUCTION AND EARTH DISTURBANCE WE DID NOT EXCAVATE THE EXISTING DRIVE. THE EXISTING FOUND IRON WAS DRIVEN DOWN AND TOPPED WITH A REMONUMENTATION CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 3/4" IRON PIPE WITH PLASTIC CAP (3). SET REMONUMENTATION CAP ON THIS EXISTING IRON.
N 70°E 16.55' SET P.K.NAIL AND REMON TAG IN N. SIDE 12" CHERRY
S 90°E 33.02' FOUND 3/4" RIGHT OF WAY IRON
S 15°E 91.80' SET P.K.NAIL AND REMON TAG IN W. SIDE 24" HICKORY
N 70°W 137.67' SET P.K.NAIL AND REMON TAG IN 18" HICKORY
N 03°W 33.01' FOUND 3/4" RIGHT OF WAY IRON

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Paul V. Schwimmer
Surveyor's Michigan License No. 24618

Date Nov 12 1997

APPROVED
DATE 11/10/97
CO. REP. K