

**SURVEY &  
REMONUMENTATION**

**COPY**

RECORDED  
WASHTENAW COUNTY, MI

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

FEB 1 8 50 AM '95

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW  
( County )

Located In:

Corner Code #

1. Public Land Survey	T	4	S	R	4	E	J-11
	T			R			
	T			R			
	T			R			
2. Property controlling in Section	S			R			
	S			R			
3. Miscellaneous Property in Sec.	S			R			
	S			R			
4. Lot No. _____, Recorded Plat _____							
5. Private Claims _____							

PEGGY M. HAINES  
COUNTY CLERK/REGISTER

- COPY -

LIBER

1 PAGE 344 RM  
COPY

Register of Deeds Stamp & File Number

I, Paul V. Schwimmer, in a field survey on October 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	28	26	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post, GLO August 31, 1819  
1) B. Oak 18" S 58" E 19 links  
2) W. Oak 24" S 37" W 28 links

No description of monument used  
3) Hickory 3" N 04' E 56.0'  
4) Nail in stump E'ly 2" hickory N 60' W 6.23'  
5) E-W fence line North 2.0'  
6) On line with E-W fence line running to west.

K.C. Sudan  
Field notes  
Date uncertain (c. 1952)

Found iron rod  
3) Hickory 3" N 04' E 56.0'  
4) Spike in clump 2" hickory N 60' W 6.23'  
5) Ely. fence line North 2.0'  
6) On line with E-W fence line running to west.  
7) N-S fence line West 3.5'

R. Timothy Tietsema LS#20712  
Survey  
10/75

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

Found 3/4" iron rod near the intersection of E-W and N-S fence lines. No remains of trees previously used as accessories to the corner.


5) E-W fence line North 2.0'  
6) On line with E-W fence line running to west.  
7) N-S fence line West 3.5'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 3/4" iron rod with 1" x 24" iron pipe with remonumentation cap set 4" above ground.

Set additional accessories:

8) Power pole West 0.88' to PK nail in N side.  
9) Angle iron fence corner West 3.63' to center.  
10) Cherry 4" East 2.31' to PK nail in S side.  
11) Oak 10" South 68.09' to PK nail in E side.



I believe this point should be accepted as the best available evidence of the original corner.

Signed by Paul V. Schwimmer

Date 12/29/94

Surveyor's Michigan License No. 24618

APPROVED

DATE 12-12-94

CO. REP. KA