

**SURVEY & REMONUMENTATION**

**COPY**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
WASHTENAW COUNTY, MI

FEB 1 8 50 AM '95

PEGGY M. HAINES  
COUNTY CLERK/REGISTER

- COPY -

For corners in **COMMISSION**

WASHTENAW (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4</u> S R <u>4</u> E	J-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER

1 PAGE 345 RM  
COPY

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	15							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Paul V. Schwimmer, in a field survey on October 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:


- Set Wood Post GLO 1819  
 1) W. Oak 12" N 08° E 56 links  
 2) B. Oak 14" S 39° W 108 links
- County Surveyor Notes 1900's  
 Set Quarter Post form which:  
 3) B. Oak 6" bears S 25° W 5 links  
 4) Elm 3" bears S 75° E 20 links  
 point falls in swamp

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

Found 2" steel post near drainage ditch. Found no evidence of witnesses. Ran traverse between the SW corner and the SE corner to confirm position of the steel post and found post to be 0.75' W and 0.36 N of the proportional location for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Even though the origin of the 2" steel pipe is unknown, without evidence to the contrary this point was accepted for the position of the corner. Set 1" x 24" iron pipe with 2" remonumentation cap inside 2" steel post.



I believe this point should be accepted as the best available evidence of the original corner.

signed by Paul V. Schwimmer Date 12/29/94  
 Surveyor's Michigan License No. 24618

APPROVED  
 DATE 12-19-94  
 CO. REP. KA