

SURVEY &
REMONUMENTATION

MAY - 1 1995

COPY

RECORDED
WASHTENAW COUNTY, MI

FEB 1 8 51 AM '95

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW (County)	Located In:	Corner Code #
1. Public Land Survey	T 4 S R 4 E	K-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

PEGGY M. HAINES
COUNTY CLERK/REGISTER

-COPY-

LIBER

1 PAGE 350 RM
COPY

Register of Deeds Stamp & File Number

I, Paul V. Schwimmer, in a field survey on October 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	18		20		21		22		23		24		
9													
10	30		28		26		27		25		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Wood post GLO 1819	Set 3/4" iron on E-W fenceline and centerline of road southerly (1) Oak 8" S 85° E 11.0' (2) Basswood 24" S 30° E 39.0' (3) Ash 8" S 80° E 16.7'	No description of corner (4) Elm 14" N 30° E 49.90' (5) E.P. East 54.95' to M.S.H.D. nail (6) Walnut 12" S 35° W 39.62' to spike (7) E.P. N 65° W 33.44'
Atwell-Hicks Notes added to survey 09/10/53	Glenn Richard LS 13040 Survey #939 L1447 P800 05/03/73	

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

Found following accessory:
2) Basswood 32" (dead) S 45° E 39.0' to PK nail on E. Side

Set corner at center of overall distance on line between section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 24" iron pipe w/ remonumentation cap for corner.


Set accessories:

- 9) Ash 6" West 18.35' to PK nail on S. side
- 10) Twin Oak 8" S 60° E 14.57' to PK nail on S. side
- 11) Ash 18" N 85° E 18.87' to PK nail N. side
- 12) Ash 12" N 85° W 10.21' to PK nail on S. side

Corner is 3.5' south of E-W fence line and outside of the gravel road.

The position of the corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by Paul V. Schwimmer Date 12/29/94
Surveyor's Michigan License No. 24618



APPROVED
DATE 12/12/94
CO. REP. fx