

SURVEY &
REMONUMENTATION

COPY

RECORDED
WASHTENAW COUNTY, MI

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 1 8 51 AM '95

For corners in **COMMISSION**

PEGGY N. HAINES
COUNTY CLERK/REGISTER

WASHTENAW (County)	Located in:	Corner Code #
1. Public Land Survey	T 4 S R 4 E	L-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

-COPY-

LISEZ

1 PAGE 352 RM
COPY

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Paul V. Schwimmer, in a field survey on September 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

Wood post GLO August 27, 1819
(1) W. Oak 20" bears N 5S' E 33 links
(2) Ash 7" bears S 03' W 23 links

Found 7/8" iron pipe
No witnesses remaining
(5) 24" Oak N 11' E 24.14'
(6) 15" Cedar S 80' W 148.76 to nail
(7) Utility pole S 01' W 35.04 to nail
(8) Twin 6" Ash S 44' W 34.40 to nail

Shown on Act 132 Survey by
R. Timothy Tietsema, RLS 20712
Li1834 P291, 1982

Grid Book
(3) W. Oak 16" S 76' W 48 links
(4) W. Oak 12" N 28' W 22 links
By surveyor named Palmer

Norman N. Fahrner LS 17620
Survey & LCRC L1-P517
11/24/71

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

Found 7/8" iron pipe 1' below road surface
(5) Oak 34" N 19' E 24.04 to nail in E. side
(6) Cedar 22" S 80' W 148.85' to nail in E. side
(7) Utility pole S 05' E 34.79' to nail in W. side

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation cap on existing iron pipe
Set additional accessories
(14) Cedar 22" S 87' W 149.52' to PK nail in N. side
(15) Twin Oak (14" & 5") S 62' W 35.57' to PK nail in N. Side

I believe this point should be accepted as the best available evidence of the original corner.



Signed by Paul V. Schwimmer

Date 12/20/94

Surveyor's Michigan License No. 24618

APPROVED
DATE 12/12/94
CO. REP. K