

SURVEY & REMONUMENTATION

MAR 09 1998

RECORDED
WASHTENAW COUNTY, MI

JAN 22 8 30 AM '98

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PEGGY M. HAINES
COUNTY CLERK/REGISTER

For corners in **SECTION**

Washtenaw (county)	Located In	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>5E</u> T _____ R _____ T _____ R _____ T _____ R _____	<u>1-9</u> _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

- COPY -

- COPY -

Liber **00002** Page **0017**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, R. Timothy Tietsema, in a field survey on 16 April, 1997, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	Name	Job No.	Description	Notes	Monuments	Distances	Remarks
7/30/1819	GLO		Fld. Notes	Set Original Corner	1) 14" W. Oak N31E 2) 8" W. Oak S88W	10 links (6.60') 17 links (11.22')	Set Post for Corners of Sec. 22, 23, 26, & 27
12/26/1933	W. J. Armstrong		Grid Book	Fnd. 2 Large Stones with Bricks	3) 6" Elm N1.5E 4) 24" Maple S58E 5) 36" Elm S21.5E 6) 15" Elm S46W	20.4' 47.2' 27.1' 35.2'	Reset with 4"x48" Concrete Monument, Stones, and Bricks.
6/3/1968	Washtenaw Engineering	JOB NO:2646	Boundary	Fnd. Iron Pipe	None		
12/30/68	Atwell-Hicks		Fld. Notes	4" Conc. Mon. with 1/4" Rerod	None		
3/30/1973	Glenn Richard	13040	LCRC	Fnd. Iron Rod in Concrete	4) 26" Maple S58E 5) 48" Maple S21E 7) Tele. Pole North	47.00' to nail 27.95' to nail (previously labeled Elm) 24.88' to nail	
6/11/1975	Norm Fahrner	17620	Boundary	Fnd. Iron Rod	4) 20" Maple S58E 5) 36" Maple S21.5E 8) 10" Walnut N20W	47.2' 27.1' 18.6'	
6/20/1975	Norm Fahrner	17620	LCRC	Fnd. 3/8" Iron Rod	4) 20" Maple S58E 5) 36" Maple S21.5E 8) 10" Walnut N20W	47.2' 27.1' 18.6'	
10/3/1986	Norm Fahrner	17620	Boundary	Fnd. 3/8" Iron Rod	4) 20" Maple S58E 5) 40" Maple S21.5E 8) 12" Walnut N20W 9) 14" Walnut S55W	47.22' to nail 27.10' to nail 18.60' to nail 66.07' to nail	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1997 LSC found a concrete monument with 3/8" iron rod from five previous witnesses (4,5,7,8 & 9).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found concrete monument with 3/8" iron rod and added Remon. Cap.
 4) 26" Maple S58E 47.51' to P.K. & r/t
 5) 48" Maple S21E 27.39' to P.K. & r/t
 7) Tele. Pole North 24.90' to P.K. & r/t
 8) 16" Walnut N15W 18.45' to P.K. & r/t
 9) 16" Walnut S70W 65.89' to P.K. & r/t

APPROVED
DATE 12/2/97
CO. REP. [Signature]

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by [Signature] Date 2 December 1997
 Surveyor's Michigan License No. 20712

