

**SURVEY &
REMONUMENTATION**

MAR 09 1998

RECORDED
#ASHTENAW COUNTY, MI

JAN 22 8 30 AM '98

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PEGGY M. HAINES
COUNTY CLERK/REGISTER

- COPY -

For corners in

<u>Washtenaw</u> (county)	Located In	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>5E</u>	<u>I-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

- COPY -
Liber **00002** Page **0018** RM
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R. Timothy Tietsema, in a field survey on 8 December, 1997, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

7/30/1819	GLO	Fld. Notes	Set Original Cor.	1) 10" Lynn N18W 2) 5" Hickory S59E	11 links (7.26') 12 links (7.92')	Set Post for 1/4 Corner between Sec. 26, & 27
10/3/1986	Norm Fahrner JOB NO:20925	17620	Boundary Set. 3/4" Iron Pipe on split between NW Corner and SW Corner.	3) 12" Oak N10E 4) 12" Maple S10E 5) 8" Maple N09E 6) 14" Elm S85E	37.11' to nail 16.70' to nail 43.06' to nail 30.79' to nail	Fence 9.7' East

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1997 LSC found a 3/4" Iron Pipe lying on the ground in the vicinity of four previous witnesses (3, 4, 5 & 6). In December of 1997 LSC re-set with a 3/4" iron pipe and Remonumentation Cap using the four previous witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" Iron Pipe with Remonumentation Cap.		North-South Fence 9.7' East
3) 14" Oak N10E	37.11' to P.K. & r/t	
4) 14" Maple S10E	16.70' to P.K. & r/t	
5) 10" Maple N09E	43.06' to P.K. & r/t	
6) 14" Elm S85E	30.79' to P.K. & r/t	

APPROVED
DATE 12/9/97
CO. REP. K

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 20712

Date 8 December 1997

