

SURVEY & REMONUMENTATION

MAR 09 1998

RECORDED
WASHTENAW COUNTY, MI

JAN 22 8 30 AM '98

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PEGGY S. HAINES
COUNTY CLERK/REGISTER

- COPY -

For corners in

Washtenaw (county)	Located In	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>5E</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

- COPY -

Liber **00002** Page **0019** RM

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R. Timothy Tietsema, in a field survey on 16 April, 1997, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	Notes	Fid. Notes	Set Original Corner	Monument	Dimensions	Other
7/30/1819	GLO			1) 10" Hickory 2) 14" Poplar	N03W 12 links (7.92') East 15 links (9.90')	Set Post for Corners of Sec. 26, 27, 34, & 35
No date		Grid Book	Iron Pipe with Stones and Bricks	3) 18" Maple 4) 18" Maple	N57W 46.7' N69.5W 74.6'	
5-15-67		Grid Book		5) 16" Walnut 6) 10" Box Elder	North 76.7' South 39.2'	4.3' North of centerline of blacktop.
6/5/1971	Washtenaw Engineering JOB NO:6882	Boundary	Fnd. Iron Pipe			
6/12/1971	Charles Wilson 13604	LCRC L.1 P.29	Fnd. 1-1/2" Iron Pipe	3) 18" Maple 4) 18" Maple 7) 3" Walnut 8) 2" Walnut 9) Power pole 10) Sycamore Multi 3"-6"	N57W 46.7' N69.5W 74.6' North 47.0' South 62.1' N'y 43.0' 39.5'	
3/30/1972	Allen Rentschler JOB NO. 72053	154114	Boundary	Fnd. Iron Pipe	3) 24" Maple 4) 24" Maple 7) 10" Walnut	N57W 46.7' N69.5W 74.6' North 47.0'
5/30/1972	Allen Rentschler 154114	LCRC L.2 P.39	Fnd. Iron Pipe	3) 24" Maple 4) 24" Maple 7) 10" Walnut	N57W 46.7" N69W 74.6' North 47.0'	

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1997 LSC found a 1/2" Iron Pipe from three previous witnesses (9,16, and 4' north of pavement centerline) and added two additional witness (17 & 18), the corner was reset with a 3/4" Iron Pipe with a Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Found 1/2" Iron Pipe, reset with 3/4" Iron Pipe with Remonumentation Cap
- 9) Power Pole N05E 43.00' to P.K. & r/t 4' north of
 - 16) 12" Ash S25E 38.13' to P.K. & r/t pavement centerline
 - 17) 8" Walnut N20E 25.11' to P.K. & r/t
 - 18) 8" Ash South 32.24' to P.K. & r/t

APPROVED
DATE 12/2/97
CO. REP. Ky

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by R. Timothy Tietsema Date 2 December 1997
Surveyor's Michigan License No. 20712

