

**SURVEY & REMONUMENTATION**

MAR 09 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
WASHTENAW COUNTY, MI

JAN 22 8 30 AM '98

PEGGY M. HAINES  
COUNTY CLERK/REGISTER

- COPY -

For corners in

Washtenaw (county)	Located In	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>5E</u>	<u>1-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 00002 Page 0021 RM

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R. Timothy Tietsema, in a field survey on 16 April, 1997, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	Surveyor	Job No.	Notes	Monument	Accessories	Measurements	Remarks
12/29/1815	GLO		Fld. Notes	Set Original Corner	1) 12" Sugar 2) 12" Sugar	S15E 10 links (6.60') N24W 38 links (25.08')	Set Post for Corner between Sec. 34 & 35
3/31/58	Atwell-Hicks F.B. 598 P. 24 E.C. McKenzie		Grid Book	1-1/2"x20" Iron Pipe	3) 16" Elm 4) Sign Post 5) Power Pole	North 44.2' S30W 29.8' S75E 122.1'	Fence line to North & in centerline of road, 16.4' east to centerline Teufel Rd. to South.
3/27/1971	Wilburn Lokey	9434	Boundary		None		
5/3/1972	John Synder	13352 JOB NO:27598	Boundary L.1397 P.244	Fnd. Iron Pipe	4) Street Sign 6) Fence Corner	S30W 29.8' S55E 52.7'	Fence line N'y 24.4'
7/3/1972	John Synder	13352 JOB NO:27723	Boundary L.1402 P.725	Fnd. Iron Pipe	4) Street Sign 6) Fence Corner	S30W 29.8' S55E 52.7'	Fence line N'y 24.4'
3/2/1979	Norm Fahrner	17620 LCRC	Fnd. 1-1/2" Iron Pipe L.5 P.215		4) Road Sign 6) 2" Steel Post 7) Fence Post 8) Iron Pipe	S25W 29.9' S55E 52.71' North 24.42 to nail East 8.60'	
8/27/79	Atwell-Hicks		Fld. Notes	Fnd. 3/4" Iron Pipe	6) 2" Steel Post 9) Fence Post 10) Sign Post	S45W --- N20W 34.1' S30W 45.2'	10'+/- west of centerline of Teufel Rd.
3/3/1979	Norm Fahrner	17620 JOB NO:17953	Boundary	Fnd. 1-1/2" Iron Pipe	4) Road Sign 6) 2" Steel Post 7) Fence Post 8) Iron Pipe	S25W 29.9' S55E 52.71' North 24.42 to nail East 8.60'	
8/7/1983	Robert Roskelly	18663	Boundary	Fnd. Iron Pipe	4) Road Sign 6) 2" Steel Post 7) Fence Post 8) Iron Pipe	S25W 29.90' S55E 52.71' North 24.42' to nail East 8.60'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1997 LSC found a 1-1/2" iron pipe from four previous witnesses (4, 5, 6, & 8), the corner was reset with a 1" iron pipe with a Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Found 1 1/2" Iron Pipe, Reset with a 1" Iron Pipe with Remonumentation Cap.
- 4) Road Sign S25W 29.65'
- 5) Power Pole S65E 122.08' to P.K. & r/t
- 6) 2" Steel Fence Post S55E 52.73'
- 8) Iron Pipe East 8.68'

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

APPROVED  
DATE 12/2/97  
CO. REP. [Signature]

Signed by [Signature]  
Surveyor's Michigan License No. 20712

Date 2 December 1997

