

SURVEY & REMONUMENTATION

MAR 09 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
*ASHTENAW COUNTY, MI

JAN 22 8 30 AM '98

PEGGY H. HAINES
COUNTY CLERK REGISTER

For corners in

Washtenaw (county)	Located In	Corner Code #
1. Public Land Survey	T 4S R 5E	J-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

- COPY -

- COPY -

Liber 00002 Page 0023 RM

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R. Timothy Tietsema, in a field survey on 16 April, 1997, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	Owner	Job No.	LCRC	Fld. Notes	Set Original Corner	Monument	Direction	Distance	Remarks
7/30/1819	GLO					1) 8" Ironwood 2) 8" Ash	N36W S22E	8 links (5.28') 33 links (21.78')	Set Post for 1/4 Corner between Sec. 26 & 35
9/23/1975	Norm Fahrner	17620		Boundary	Fnd. 1" Iron Pipe	3) 24" Basswood 4) South end 12" CMP 5) West end 12" CMP	S05E S60E North	16.7' 30.3' 35.3'	
11/30/1987	Norm Fahrner	17620		Boundary	Fnd. 1" Iron Pipe	3) 26" Basswood 4) South end 12" CMP 6) Fence post 7) 12" Ash	S05E S60E N10E N05W	16.65' to nail 30.3' 44.73' to nail 67.37' to nail	
10/2/1995	Glenn Richard	13040	LCRC L.8 P.159		Fnd. 1-1/4" Iron Pipe	3) 30" Basswood 7) 14" Walnut 8) Elec. Pole 9) Elec. Pole 10) SE Cor Sec 26 11) SW Cor Sec 26 12) Capped Iron #20712 on Section Line	S10E N10W N75W N75E East West East	16.56' to nail 67.31' to nail (previously labeled Ash) 73.40' to nail & disc 160.72' to nail & disc 2642.56' 2634.02' 1323.61'	Corner 1' S. of pvmt.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1997 LSC found a 1" Iron Pipe from four previous witnesses (3, 4, 5, & 7) and added one additional witness (13), a remonumentation cap was set on the existing iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" Iron Pipe and added Remonumentation Cap.			
3) 48" Basswood	South	16.56' to P.K. & r/t	Corner 0.5' South of pavement
4) South end 12" CMP	S70E	30.19'	
5) West end 12" CMP	N10E	35.26'	
7) 15" Elm	N05W	67.39' to P.K. & r/t (previously labeled Ash & Walnut)	
13) North end 12" CMP	N50E	42.37'	

APPROVED
DATE 12/2/97
CO. REP. [Signature]

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 20712

Date 2 December 1997

