

SURVEY & REMONUMENTATION

MAR 09 1998

SECTION

RECORDED
WASHTENAW COUNTY, MI

JAN 22 8 30 AM '98

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PEGGY A. HAINES
COUNTY CLERK/REGISTRAR

For corners in

Washtenaw (county)	Located In	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>5E</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- COPY -

- COPY -

Liber **00002** Page **0024** RM

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R. Timothy Tietsema, in a field survey on 16 April, 1997, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	Owner	Job No.	Boundary	Fld. Notes	Set Original Corner	Monument	Dimensions	Notes
11/29/1815	GLO					1) 12" Beech 2) 12" Lymn	N54W 15 links (9.90') S34E 41 links (27.06')	Set Post for S 1/4 Corner Section 35
3/31/58	Atwell-Hicks F.B. 598 P.24			Grid Book & Fld. Notes	Set 3/4" x20" Iron Pipe	3) 12" Elm 4) Tele. Pole	N25W 24.7' N40E 55.2'	On fence line North & 24.5 North of fence on South side of road, 207.0' East to fence line South (Lenawee).
5/3/1972	John Synder JOB NO. 27598	13352	L.1397 P.244	Boundary	Fnd. Iron Pipe	3) Elm Stump	24.7'	Fence line N'y & E'ly 20.0'
7/3/1972	John Synder JOB NO. 27723	13352	L.1402 P.725	Boundary	Fnd. Iron Pipe	3) Elm Stump	24.7'	Fence line N'y & E'ly 20.0'
10/2/1995	R.T. Tietsema JOB NO. 10092	20712		Boundary	Fnd. 1" Iron Pipe	5) Power Pole 6) 8" Elm 7) 6" Elm	N87W 209.00' N80E 83.79' EAST 140.15'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1997 LSC found a 1" Iron Pipe from two previous witnesses (5 & 6) and added two additional witness (7 & 8).


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Found 1" Iron Pipe and added Remonumentation Cap.
- 6) 8" Elm N80E 83.79' to P.K. & r/t
- 7) 6" Elm EAST 140.15' to P.K. & r/t
- 8) Utility Pole S80W 157.47' to P.K. & r/t with GTE Riser
- 9) 5" White Pine N40E 44.72' to P.K. & r/t

APPROVED
DATE 12/2/97
CO. REP. [Signature]

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 20712



Date 2 December 1997